



Bid Questions and Answers Report

Date & Time:

7/29/2020 9:25:30 AM

District Address: District 3 Construction Office, located at 1074 Highway 90 East, Chipley, FL 32428

District Phone: (850) 415-9713

Proposal: T3717

Project: 437202-1-52-01

Letting Date: 7/29/2020

Localtion: CENTRAL OFFICE

Description: CR 278 (PIONEER RD)

Question: 30449: Can the bridge culvert be precast per Standard 400-291 & 400-292? Posted: 7/8/2020 9:14:11 AM

Answer: Yes, a precast box culvert using Standard Index 400-291 and 400-292 is acceptable at this location. Long-term differential settlement is estimated to be less than 0.5 inches over the length of the culvert. Status: ANSWER PUBLISHED
Posted: 7/8/2020 10:53:50 AM