



Bid Questions and Answers Report

Date & Time:

5/20/2020 8:05:55 AM

District Address: District 5 Construction Office, located at 719 South Woodland Blvd, Deland, FL 32720

District Phone: (386) 943-5350

Proposal: T5676

Project: 439139-1-52-01

Letting Date: 5/20/2020

Localtion: CENTRAL OFFICE

Description: SR 25 (US 27)

Question: 29633: The plan sheets indicate 19 (50ft long) station ranges/26 lane locations for pavement design transitions. Posted: 4/23/2020 1:36:55 PM

Can you clarify the limits of work by correlating the Typical Sections Details Cross-Slope Correction sheets 7 through 11, so that the station ranges will match exactly those station ranges as shown in the plan sheets.

Answer: The Pavement Design Transition areas shown on the Roadway Plan sheets indicate areas of cross slope correction transitions. A 50-ft hatched area is shown to overlap a begin station and/or an end station of the cross slope correction ranges, as shown on Sheets 7 through 11. Status: ANSWER PUBLISHED
Posted: 5/1/2020 1:20:06 PM

Question: 29743: Please reference the summary of quantities for OBG 1. Area ID 38556 seems to reference a 2 foot paved inside shoulder adjacent to a mill and resurface area. Per the typical sections, should this be mandatory B-12.5? If so, please consider revising the bid item quantities to reflect the change. Posted: 5/5/2020 8:56:15 AM

Answer: See Plans Revision Number 1. Status: ANSWER PUBLISHED
Posted: 5/13/2020 11:01:22 AM

Question: 29747: After reviewing the CAD file provided for performance turf, it seems the pay item quantity does not include type 1 shoulder treatment adjacent to mill and resurface areas. Please clarify how the department will quantify and pay for the type 1 shoulder treatment required for the project. Posted: 5/5/2020 8:56:01 AM

Answer: See Plans Revision Number 1. Status: ANSWER PUBLISHED
Posted: 5/13/2020 11:02:21 AM

Question:	29754: Please reference the summary of quantities for Optional Base Group 01. Area ID 38476 (98.4 SY) seems to be an error. The plan sheet does not show work at the referenced station. Please verify and, if it is an error, please consider revising the bid item quantity as needed.	Posted:	5/5/2020 12:19:56 PM
Answer:	See Plans Revision Number 1.	Status:	ANSWER PUBLISHED
		Posted:	5/13/2020 11:03:13 AM
Question:	29755: After reviewing the summary of quantities and the CAD file, there seem to be three areas that have not been quantified for Option Base Group 9: 2615+67 to 2620+47 (LT - 249 SY); 2626+60 to 2628+21 (RT/Median - 89 SY); 2673+30 to 2674+41 (LT - 147 SY). Please verify and consider adjusting the bid item quantity as needed.	Posted:	5/5/2020 12:20:08 PM
Answer:	See Plans Revision Number 1.	Status:	ANSWER PUBLISHED
		Posted:	5/13/2020 11:03:55 AM
Question:	29890: Per specification, is the 1000 CY of milled material to be retained by the Department, a not to exceed quantity? What will the process be to determine the 1000 CY?	Posted:	5/13/2020 11:15:56 AM
Answer:	Acceptance of additional milled material that exceeds 1,000 CY will be considered at the discretion of the Department. Verification for quantities will be based on truck measurements and visual capacity of the truck. Contact information for Leesburg Operations is as follows: Ed Petersen at (352) 326-7729 and (352) 409-1845.	Status:	ANSWER PUBLISHED
		Posted:	5/15/2020 1:52:51 PM
Question:	29891: Typical Sheet 5 states Optional Base Group 4 will be Type B-12.5 only, for the Widening/Reconstruction of the Median Crossovers and Turnouts. Sheet SQ-12 does not specify this in the design notes. What will be expected of the contractor in these areas?	Posted:	5/13/2020 11:22:28 AM
Answer:	All Optional Base Group 4 required for the project is restricted to Type B-12.5 only and will be paid for under Pay Item Number 285-704.	Status:	ANSWER PUBLISHED
		Posted:	5/15/2020 1:09:11 PM
Question:	29892: Which typical sheet designates Optional Base Group 2?	Posted:	5/13/2020 11:23:56 AM

Answer: Pay Item 285-702 is to be used for Optional Base Group 1 (Type B-12.5 Only), as shown on the Design Notes column on the Summary of Quantities sheets. See Sheets 5 through 11 and SQ-11 through SQ-12 for locations.

Status: ANSWER PUBLISHED

Posted: 5/15/2020 1:40:57 PM