

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

|                        |                |                            |                 |             |
|------------------------|----------------|----------------------------|-----------------|-------------|
| Letting:               | CT200429       | Call Order: 006            | Proposal: T3747 | District:03 |
| Counties:              | HOLMES         |                            |                 |             |
| Road Name:             | SR 2           |                            |                 |             |
| Limits:                | AT CR 173      |                            |                 |             |
| Project(s):            | 44173515201(*) | Federal Aid No:            | D319126B        |             |
| Total Roadway Length:  | 0.135 Miles    | Contract Days:             | 120             |             |
| Total Bridge Length:   | 0.000 Miles    | Letting Date:              | 04/29/20        |             |
| Total Proposal Length: | 0.135 Miles    | Contract Execution Days:   | 10              |             |
|                        |                | Special Start Date:        | N/A             |             |
|                        |                | Aquis/Flexible Start Time: | 90 day Other    |             |

Proposal Budget Estimate: \$530,605.00

Please read the full advertisement

**Description:**

The improvements under this contract consist of intersection realignment, milling and resurfacing, overbuild, widening, drainage, signing and pavement markings and signalization along SR 2 at CR 173 in Holmes County, Florida.

**Call Order: 006 Proposal: T3747**

| ALT                         | Item         | Description   | Unit | Quantity  |
|-----------------------------|--------------|---|------|-----------|
| <b>Section 0001 Roadway</b> |              |   |      |           |
|                             | 0101- 1-     | MOBILIZATION (44173515201)                                    | LS   | 1.000     |
|                             | 0102- 1-     | MAINTENANCE OF TRAFFIC (44173515201)                          | LS   | 1.000     |
|                             | 0102- 2- 1   | SPECIAL DETOUR 1 (44173515201)                                | LS   | 1.000     |
|                             | 0102- 2- 2   | SPECIAL DETOUR 2 (44173515201)                                | LS   | 1.000     |
|                             | 0102- 60-    | WORK ZONE SIGN  | ED   | 4,580.000 |
|                             | 0102- 61-    | BUSINESS SIGN   | EA   | 40.000    |
|                             | 0102- 71- 13 | TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE                 | LF   | 576.000   |
|                             | 0102- 71- 23 | TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE             | LF   | 420.000   |
|                             | 0102- 74- 1  | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD        | ED   | 1,780.000 |
|                             | 0102- 78-    | TEMPORARY RETROREFLECTIVE PAVEMENT MARKER                     | EA   | 877.000   |
|                             | 0104- 10- 3  | SEDIMENT BARRIER  | LF   | 410.000   |
|                             | 0104- 18-    | INLET PROTECTION SYSTEM                                       | EA   | 3.000     |
|                             | 0107- 1-     | LITTER REMOVAL  | AC   | 3.760     |
|                             | 0107- 2-     | MOWING  | AC   | 3.930     |
|                             | 0110- 1- 1   | CLEARING & GRUBBING (44173515201)                             | LS   | 1.000     |
|                             | 0120- 1-     | REGULAR EXCAVATION  | CY   | 415.000   |
|                             | 0120- 2- 2   | BORROW EXCAVATION, TRUCK MEASURE                              | CY   | 368.000   |
|                             | 0285-701-    | OPTIONAL BASE, BASE GROUP 01                                  | SY   | 291.000   |
|                             | 0285-706-    | OPTIONAL BASE, BASE GROUP 06                                  | SY   | 630.000   |
|                             | 0327- 70- 12 | MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH                     | SY   | 3,136.000 |
|                             | 0334- 1- 52  | SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22              | TN   | 183.200   |
|                             | 0337- 7- 80  | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22 | TN   | 271.600   |
|                             | 0430-174-118 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD                 | LF   | 43.000    |
|                             | 0430-984-125 | MITERED END SECTION, OPTIONAL ROUND, 18" SD                   | EA   | 2.000     |
|                             | 0430-984-129 | MITERED END SECTION, OPTIONAL ROUND, 24" SD                   | EA   | 2.000     |

**Call Order: 006 Proposal: T3747**

| ALT                               | Item         | Description  | Unit | Quantity  |
|-----------------------------------|--------------|--|------|-----------|
|                                   | 0570- 1- 1   | PERFORMANCE TURF   | SY   | 1,857.000 |
|                                   | 0570- 1- 2   | PERFORMANCE TURF, SOD  | SY   | 677.000   |
|                                   | 0710- 11-101 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"                                    | GM   | 0.862     |
|                                   | 0710- 11-125 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"        | LF   | 140.000   |
|                                   | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"                                   | GM   | 0.841     |
|                                   | 0999- 25-    | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44173515201)                                     | LS   | 1.000     |
| <b>Section 0002 Signing</b>       |              |  |      |           |
|                                   | 0546- 71- 1  | RAISED RUMBLE STRIP SET- PERMANENT   | EA   | 8.000     |
|                                   | 0700- 1- 11  | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF  | AS   | 2.000     |
|                                   | 0700- 1- 50  | SINGLE POST SIGN, RELOCATE   | AS   | 5.000     |
|                                   | 0700- 1- 60  | SINGLE POST SIGN, REMOVE   | AS   | 6.000     |
|                                   | 0701- 18-101 | PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"                       | GM   | 0.392     |
|                                   | 0705- 11- 2  | DELINEATOR, NON-FLEXIBLE   | EA   | 10.000    |
|                                   | 0710- 90-    | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44173515201)                                   | LS   | 1.000     |
|                                   | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK                   | LF   | 63.000    |
|                                   | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"                                 | GM   | 0.073     |
|                                   | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"                                | GM   | 0.430     |
| <b>Section 0003 Signalization</b> |              |  |      |           |
|                                   | 0630- 2- 11  | CONDUIT, FURNISH & INSTALL, OPEN TRENCH  | LF   | 652.000   |
|                                   | 0630- 2- 12  | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE   | LF   | 188.000   |
|                                   | 0632- 7- 1   | SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL                       | PI   | 1.000     |
|                                   | 0632- 7- 2   | SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL                                    | LF   | 779.000   |
|                                   | 0632- 7- 6   | SIGNAL CABLE, REMOVE- INTERSECTION   | PI   | 1.000     |
|                                   | 0634- 4-152  | SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL   | PI   | 1.000     |
|                                   | 0635- 2- 11  | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE   | EA   | 8.000     |
|                                   | 0639- 1-112  | ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY | AS   | 1.000     |
|                                   | 0639- 2- 1   | ELECTRICAL SERVICE WIRE, FURNISH & INSTALL   | LF   | 10.000    |
|                                   | 0639- 3- 12  | ELECTRICAL SERVICE DISCONNECT, F&I, CABINET  | EA   | 1.000     |
|                                   | 0641- 2- 12  | PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE                                   | EA   | 1.000     |
|                                   | 0641- 2- 17  | PRESTRESSED CONCRETE POLE, F&I, TYPE P-VII   | EA   | 2.000     |
|                                   | 0641- 2- 80  | PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER                   | EA   | 2.000     |
|                                   | 0650- 1- 12  | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 1 SECTION, 2-4 WAY                 | AS   | 3.000     |
|                                   | 0660- 1-105  | LOOP DETECTOR, INDUCTIVE, F&I, TYPE 5, 2CHANNEL, SOLID STATE, SHELF MOUNTED              | EA   | 2.000     |
|                                   | 0660- 2-102  | LOOP ASSEMBLY, F&I, TYPE B   | AS   | 2.000     |
|                                   | 0660- 2-106  | LOOP ASSEMBLY, F&I, TYPE F   | AS   | 2.000     |
|                                   | 0670- 5-112  | TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 2 PREEMPTION                                     | AS   | 1.000     |
|                                   | 0700- 12- 11 | SIGN BEACON, F&I GROUND MOUNT- AC POWERED, ONE BEACON                                    | AS   | 2.000     |