

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT200429	Call Order: 007	Proposal: T3748	District:03
Counties:	DIST/ST-WIDE			
Road Name:	SAFETY PROJECT			
Limits:	AT VARIOUS LOCATIONS AS LISTED IN THE PLANS			
Project(s):	44404215201(*)	Federal Aid No:	D319147B	
Project(s):	44404225201	Federal Aid No:	D319148B	
Total Roadway Length:	N/A Miles	Contract Days:	75	
Total Bridge Length:	N/A Miles	Letting Date:	04/29/20	
Total Proposal Length:	N/A Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days Acquis.	
Proposal Budget Estimate:	\$915,020.00			

Please read the full advertisement

Description:

The improvements under this contract consist of installing signing and pavement markings along curves on interstate ramps (444042-1-52-01) and state roads (444042-2-52-01) to comply with recent updates to the Manual on Uniform Traffic Control Devices (MUTCD) throughout District 3.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 007 Proposal: T3748

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44404215201)	LS	1.000
	0101- 1-	MOBILIZATION (44404225201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44404215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44404225201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,372.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,655.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44404215201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44404225201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	252.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	315.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 32	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, 12-20 SF	AS	4.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	57.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	75.000
	0700- 1- 80	SINGLE POST SIGN, REPAIR	AS	1.000
	0700- 1- 87	SINGLE POST SIGN, REPAIR- REPLACE POST, USE EXISTING SIGN PANEL	AS	3.000
	0700- 1-101	SINGLE POST SIGN, STRAIGHTEN & RESET POST- HURRICANE REPAIRS	AS	1.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	34.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	2.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	6.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	28.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	2.000
	0705- 11- 4	DELINEATOR, FLEXIBLE HIGH PERFORMANCE 48"	EA	2,765.000
	0706- 1- 1	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS	EA	51.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	6.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	1,098.000
	0711- 12-122	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 8" FOR MAINTENANCE USE	LF	111.000
	0711- 12-123	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 12" FOR CROSS WALK OR ROUNDABOUT- MAINTENANCE USE ONLY	LF	110.000
	0711- 12-170	THERMOPLASTIC, REFURBISH, WHITE, ARROWS	EA	15.000