

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT200429	Call Order: 010	Proposal: T4549	District:04
Counties:	BROWARD			
Road Name:	NW 62ND AVE AND TURTLE CR RD			
Limits:	FROM BLAND RD TO SAMPLE RD AND FROM SAMPLE RD TO SR 7 (US 441)			
Project(s):	43783015201(*)	Federal Aid No:	D419084B	
Total Roadway Length:	0.825 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	04/29/20	
Total Proposal Length:	0.825 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Calendar Days	

Proposal Budget Estimate: \$1,315,758.00

Please read the full advertisement

Description:

The improvements under this contract consist of, but not limited to, milling and resurfacing, concrete (curb, curb and gutter, sidewalk and driveways), signing (single post), pavement markings (painted and thermoplastic, detectable warnings), manhole adjustments, selective clearing and grubbing (tree removal, tree protection, branch pruning), pull boxes, and sod, along NW 62nd.

Call Order: 010 Proposal: T4549

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43783015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43783015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	48.000
	0102- 60-	WORK ZONE SIGN	ED	16,216.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	63,289.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	222.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,186.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	388.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	39.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.730
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,948.000
	0120- 1-	REGULAR EXCAVATION	CY	1,154.700
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	1,155.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	33,733.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	95.300
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	2,872.500
	0425- 5-	MANHOLE, ADJUST	EA	10.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	704.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	4,653.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	390.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	416.000
	0527- 2-	DETECTABLE WARNINGS	SF	345.000

Call Order: 010 Proposal: T4549

ALT	Item	Description	Unit	Quantity
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	5,983.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43783015201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	19.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	388.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43783015201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,401.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	208.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.750
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	61.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	3.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.167
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	517.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	33.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	33.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.512
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.018
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.271
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.069
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.359
	0920-711- 3	GREEN COLORED PAVEMENT MARKING, BIKE LANE, PROJECT 437830-1-52-01	SF	5,080.000
Section 0003 Signalization				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	5.000