

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: CT200429 Call Order: 013 Proposal: T6460 District:06  
 Counties: MIAMI-DADE  
 Road Name: SR 7 (US 441) (NW 7 AVE)  
 Limits: FROM LITTLE RIVER DR TO S OF BISCAYNE CANAL  
 Project(s): 43081735201 Federal Aid No: D619021B  
 Project(s): 43081735601 Federal Aid No: N/A  
 Project(s): 43081745201(\*) Federal Aid No: D619022B  
 Project(s): 43081745202 Federal Aid No: D619022B  
 Project(s): 43081745601 Federal Aid No: N/A  
 Total Roadway Length: 7.192 Miles Contract Days: 500  
 Total Bridge Length: 0.028 Miles Letting Date: 04/29/20  
 Total Proposal Length: 7.220 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 30 Calendar Days

Proposal Budget Estimate: \$10,293,285.00

Please read the full advertisement

Description: A+B Bidding/Incentive-Disincentive FLEXIBLE START

The improvements under this contract consist of milling and resurfacing along SR 7 (US 441) (NW 7th Ave.).

**NOTE: This is a cost plus time proposal(A+B). The following sites are cost plus time sites.**

Site	Description	Road Cost Per Day	Maximum Days
00	Contract Time	8000.00	500

**Call Order: 013 Proposal: T6460**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43081735201)	LS	1.000
	0101- 1-	MOBILIZATION (43081745201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43081735201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43081745201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	56.700
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	336.000
	0102- 60-	WORK ZONE SIGN	ED	68,820.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	440,435.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	15,630.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	2,106.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	4,060.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	4,592.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,058.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	5,545.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	5,545.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.042
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.042

**Call Order: 013 Proposal: T6460**

ALT	Item	Description	Unit	Quantity
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.084
	0104- 18-	INLET PROTECTION SYSTEM	EA	134.000
	0107- 1-	LITTER REMOVAL	AC	246.620
	0107- 2-	MOWING	AC	45.300
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43081735201)	LS	1.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43081745201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43081735201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43081745201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	12,406.000
	0120- 1-	REGULAR EXCAVATION	CY	13,142.000
	0120- 6-	EMBANKMENT	CY	1,975.500
	0160- 4-	TYPE B STABILIZATION	SY	6,707.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	6,707.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	1,853.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	190,876.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	11,668.900
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	10,770.700
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	8.000
	0425- 1-331	INLETS, CURB, TYPE P-3, <10'	EA	2.000
	0425- 1-341	INLETS, CURB, TYPE P-4, <10'	EA	5.000
	0425- 1-345	INLETS, CURB, TYPE P-4, PARTIAL	EA	40.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	18.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	4.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	3.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	6.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0425- 2- 72	MANHOLES, J-7, >10'	EA	1.000
	0425- 2- 73	MANHOLES, J-7, PARTIAL	EA	35.000
	0425- 5-	MANHOLE, ADJUST	EA	35.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	170.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	2,879.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	20.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	24,813.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	21.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	11,328.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	5,387.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	4,667.000
	0523- 1- 3	PATTERNED PAVEMENT, VEHICULAR AREAS- GREEN BIKE LANE	SY	2,645.000
	0527- 2-	DETECTABLE WARNINGS	SF	2,866.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	10,742.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	388.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	300.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	9.000

**Call Order: 013 Proposal: T6460**

ALT	Item	Description	Unit	Quantity
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	16.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	16.000
	0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	4.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.040
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,084.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	840.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	16.354
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	143.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	17.394
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43081735201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43081745201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43081745202)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	321.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	72.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	27.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	12.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	255.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	21.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	445.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43081735201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43081745201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43081745202)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	15,740.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	4,799.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	2,694.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	4.050
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	65.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	238.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	198.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.047
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	5,974.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	139.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	137.000

**Call Order: 013 Proposal: T6460**

ALT	Item	Description	Unit	Quantity
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	5.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	12.521
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.613
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	7.619
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.012
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	8.140
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.055
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.015
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.117
<b>Section 0003 Lighting</b>				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	30.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	167.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	3,354.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	3,060.000
	0715- 4- 32	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 35' MOUNTING HEIGHT	EA	1.000
	0715- 4- 71	LIGHT POLE COMPLETE, REMOVE POLE, FOUNDATION REMAINS	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	1.000
<b>Section 0004 Signalization</b>				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,055.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	2,665.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	183.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	210.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	38.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	1.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	13.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION- BOLT ON ATTACHMENT	EA	2.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	50.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	14.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	76.000

**Call Order: 013 Proposal: T6460**

ALT	Item	Description	Unit	Quantity
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	44.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	13.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	47.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	57.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	46.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	20.000
	0670- 5-140	TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL MODEL 207C	AS	1.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	10.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	3.000
	0700- 5- 50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	1.000
<b>Section 0005 Landscape / Peripheral</b>				
	0580- 2- 1	LANDSCAPE- RELOCATE TREE, PALMS <14' OF CLEAR TRUNK	EA	6.000
	0580- 2- 2	LANDSCAPE- RELOCATE TREE, PALMS >14' OF CLEAR TRUNK	EA	4.000
	0580- 2- 4	LANDSCAPE- RELOCATE TREE, TREES <5" CALIPER	EA	7.000
<b>Section 0006 Utilities</b>				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43081735601)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43081745601)	LS	1.000
	1060- 15-	UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	EA	72.000
	1080- 24-500	UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	EA	116.000