

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT200429 Call Order: 016 Proposal: T7451 District:07
Counties: PINELLAS
Road Name: INTERSECTION LIGHTING
Limits: AT MULTIPLE LOCATIONS AS LISTED IN PLANS
Project(s): 43982985201(*) Federal Aid No: D719048B
Total Roadway Length: 20.235 Miles Contract Days: 170
Total Bridge Length: 0.000 Miles Letting Date: 04/29/20
Total Proposal Length: 20.235 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 120 Calendar Days
Proposal Budget Estimate: \$680,000.00

Please read the full advertisement

Description: FLEXIBLE START

The improvements under this contract consist of providing intersection lighting at various signalized intersections.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 016 Proposal: T7451

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43982985201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43982985201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,190.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,230.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	138.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	170.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	170.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,714.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	32.000
	0110- 1- 1	CLEARING & GRUBBING (43982985201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	84.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	68.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43982985201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	680.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,375.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	61.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	10.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	11,055.000
	0715- 4- 12	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT	EA	1.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	13.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	17.000
	0715- 4- 60	LIGHT POLE COMPLETE, RELOCATE	EA	5.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	86.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	17.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	36.000