

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT200429 Call Order: 017 Proposal: T7452 District:07
 Counties: CITRUS
 Road Name: PLEASANT GROVE ELEMENTARY SIDEWALK
 Limits: FROM GROVE MANOR BLVD TO W MAIN ST AND FROM PLEASANT GROVE RD E TO EXISTING SIDEWALK
 Project(s): 43969915201(*) Federal Aid No: D719050B
 Total Roadway Length: 1.141 Miles Contract Days: 90
 Total Bridge Length: 0.000 Miles Letting Date: 04/29/20
 Total Proposal Length: 1.141 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 60 Calendar Days

Proposal Budget Estimate: \$600,000.00

Please read the full advertisement

Description:

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at:
<https://www.fdot.gov/equalopportunity/bdi.shtml>.

For more information about bidding on BDI projects, please see the training guide located at:
<http://www.cmdp-bgp.com/bdi-projects.html>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at:
<https://www.fdot.gov/equalopportunity/bdi.shtml>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: fdot.bdi@dot.state.fl.us.

All Sublet work must be contracted to a small business or businesses as defined by the Department. The subcontractor must also submit a notarized Small Business Affidavit Form provided by the Department prior to the start of work.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the project's major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the Expedite application.

BDI Reference Sheet may be found at: <https://www.fdot.gov/equalopportunity/bdi.shtml>

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

The improvements under this contract consist of the addition of approximately 6,020 LF of sidewalk, associated drainage, and signing and marking.

Call Order: 017 Proposal: T7452

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43969915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43969915201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,490.000

Call Order: 017 Proposal: T7452

ALT	Item	Description	Unit	Quantity
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	12,690.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	228.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	194.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,276.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0110- 1- 1	CLEARING & GRUBBING (43969915201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	5.000
	0120- 1-	REGULAR EXCAVATION	CY	1,419.000
	0120- 6-	EMBANKMENT	CY	704.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	1,261.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	104.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	3.300
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	3.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	2.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	2.000
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	260.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	118.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	280.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	4.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	56.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	4.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	1.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	5.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	39.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	7.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	2,979.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	727.000
	0527- 2-	DETECTABLE WARNINGS	SF	550.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	2.000
	0530- 74-	BEDDING STONE	TN	1.400
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	10,215.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	1,781.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43969915201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	4.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	25.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	1,301.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	815.000

Call Order: 017 Proposal: T7452

ALT	Item	Description	Unit	Quantity
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	26.000