

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT200826	Call Order: 004	Proposal: T3700	District:03
Counties:	BAY			
Road Name:	SR 30 (US 98B)			
Limits:	AT VARIOUS LOCATIONS AS LISTED IN THE PLANS			
Project(s):	43811115201(*)	Federal Aid No:	D320031B	
Project(s):	44038615201	Federal Aid No:	D320040B	
Project(s):	44038625201	Federal Aid No:	D320041B	
Project(s):	44038635201	Federal Aid No:	D320042B	
Total Roadway Length:	0.770 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	08/26/20	
Total Proposal Length:	0.770 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Day Standard	
Proposal Budget Estimate:	\$961,137.00			

Please read the full advertisement

Description:

The improvements under this contract consist of lead project FPID 438111-1-52-01 construction of six-foot sidewalk on SR 30 (US 98B) from CR 22A Bob Little Road to SR 30A (US 98) Tyndall Parkway. Improvements also include goes with FPID 440386-1-52-01 consist of the construction of six-foot sidewalk on SR 30 (US 98B) East Highway 98 from Park Entrance to CR 22A Bob Little Road. Improvements also include goes with FPID 440386-2-52-01 consist of the construction of six-foot sidewalk on West Street from SR 30 (US 98B) East Highway 98 to Cedar Street. Improvements also include goes with FPID 440386-3-52-01 consist of the construction of six-foot sidewalk on CR 22A Bob Little Road from SR 30 (US 98B) East Highway 98 to Lake Drive in Bay County. Incidental work includes minor drainage improvements and signing and pavement markings.

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at: <https://www.fdot.gov/equalopportunity/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at: <http://www.cmdp-bgp.com/bdi-projects.html>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: fdot.bdi@dot.state.fl.us.

All Sublet work must be contracted to a small business or businesses as defined by the Department. The subcontractor must also submit a notarized Small Business Affidavit Form provided by the Department prior to the start of work.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the project's major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the AASHTOWare Project Bid application.

BDI Reference Sheet may be found at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

Call Order: 004 Proposal: T3700

Call Order: 004 Proposal: T3700

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43811115201)	LS	1.000
	0101- 1-	MOBILIZATION (44038615201)	LS	1.000
	0101- 1-	MOBILIZATION (44038625201)	LS	1.000
	0101- 1-	MOBILIZATION (44038635201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43811115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44038615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44038625201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44038635201)	LS	1.000
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (43811115201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	11,520.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	50,940.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,160.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	5,400.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	3,860.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,496.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	180.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,500.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	9.000
	0107- 1-	LITTER REMOVAL	AC	30.530
	0107- 2-	MOWING	AC	17.310
	0110- 1- 1	CLEARING & GRUBBING (43811115201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44038615201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44038625201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44038635201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,133.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	14.000
	0120- 1-	REGULAR EXCAVATION	CY	611.500
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	697.800
	0120- 6-	EMBANKMENT	CY	6.600
	0160- 4-	TYPE B STABILIZATION	SY	1,259.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	10.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	107.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	1,390.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	104.100
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	25.400
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	5.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	5.000
	0400- 2- 12	CONCRETE, CLASS II, TRENCH SLAB	CY	0.400
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	5.000
	0425- 1-575	INLETS, DITCH BOTTOM, TYPE G, PARTIAL	EA	1.000

Call Order: 004 Proposal: T3700

ALT	Item	Description	Unit	Quantity
	0425- 1-910	INLETS, CLOSED FLUME	EA	3.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0425- 4-	INLETS, ADJUST	EA	3.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	8.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	249.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	16.000
	0430-200- 25	FLARED END SECTION, CONCRETE, 18"	EA	1.000
	0430-518-100	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-610-125	U-ENDWALL, INDEX261/430-011, 1:4 SLOPE, 18"PIPE	EA	1.000
	0430-963- 1	PVC PIPE FOR BACK OF SIDEWALK, 4"	LF	56.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	11.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	63.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,456.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	22.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,949.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	2,439.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	13.000
	0527- 2-	DETECTABLE WARNINGS	SF	441.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,493.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43811115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44038615201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	4.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	11.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.004
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.009
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	143.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.007
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	830.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	109.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	169.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	306.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	144.000