

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT200826 Call Order: 007 Proposal: T6505 District:06
 Counties: MIAMI-DADE
 Road Name: SR 94 (KENDALL DR/SW 88 ST)
 Limits: FROM E OF SW 150TH AVE TO E OF SW 132ND AVE
 Project(s): 43326435201(*) Federal Aid No: D619064B
 Project(s): 43326435202 Federal Aid No: D619064B
 Project(s): 43326435601 Federal Aid No: N/A
 Project(s): 43326445201 Federal Aid No: D619065B
 Total Roadway Length: 2.098 Miles Contract Days: 350
 Total Bridge Length: 0.000 Miles Letting Date: 08/26/20
 Total Proposal Length: 2.098 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 60 Calendar Days
 Proposal Budget Estimate: \$5,011,499.00

Please read the full advertisement

Description: Incentive / Disincentive

The improvements under this contract consist of milling and resurfacing along SR 94 (Kendall Dr./SW 88 St.) and intersection improvements between SW 149th Ave. and 147th Ave.

Call Order: 007 Proposal: T6505

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43326435201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43326435202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43326445201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	776.000
	0102- 60-	WORK ZONE SIGN	ED	16,260.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	178,270.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	3,090.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	2,730.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	728.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	2,100.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	2,100.000
	0102-115-	TYPE III BARRICADE	ED	3,620.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	200.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	76.000
	0107- 1-	LITTER REMOVAL	AC	51.080
	0107- 2-	MOWING	AC	12.660
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43326435201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43326435201)	LS	1.000

Call Order: 007 Proposal: T6505

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (43326435201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43326435202)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43326445201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.010
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,290.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43326445201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	1,362.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	1,372.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	602.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	110,889.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	9,516.500
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	6,214.500
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	2.300
	0425- 1-204	INLETS, CURB, TYPE 9, J BOT, >10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-352	INLETS, CURB, TYPE P-5, >10'	EA	3.000
	0425- 1-422	INLETS, CURB, TYPE J-2, >10'	EA	1.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	3.000
	0425- 1-452	INLETS, CURB, TYPE J-5, >10'	EA	5.000
	0425- 1-921	INLETS, ADJACENT BARRIER, <=10'	EA	1.000
	0425- 2- 42	MANHOLES, P-7, >10'	EA	8.000
	0425- 2- 72	MANHOLES, J-7, >10'	EA	3.000
	0425- 5-	MANHOLE, ADJUST	EA	52.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	12.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	239.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	265.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	248.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	190.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,030.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	2,713.000
	0520- 5- 42	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 6' WIDE	LF	415.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	20.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	521.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,157.000
	0527- 2-	DETECTABLE WARNINGS	SF	530.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	146.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	260.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	12.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	12.000
	0695- 7-171	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 4, 2 PLANE BACK, BASE MOUNT	EA	2.000

Call Order: 007 Proposal: T6505

ALT	Item	Description	Unit	Quantity
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	5.477
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.222
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	4,280.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	925.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,098.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	11.603
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.169
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	117.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.282
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	439.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.250
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43326435201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43326435202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43326445201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	72.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	62.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	5.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	5.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	4.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	5.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	153.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43326435201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,324.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	932.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,155.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.166
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	120.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	379.000

Call Order: 007 Proposal: T6505

ALT	Item	Description	Unit	Quantity
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.249
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	3,647.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.513
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	1.181
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",1C-30 SKIP OR 3-9 LANE DROP	GM	7.803
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.350
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.003
Section 0003 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	926.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	31.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	3,858.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	68.000
	0715- 21- 2	LIGHTING REPAIRS AND RETROFITS, LED RETROFIT KIT FOR EXISTING LUMINAIRE	EA	68.000
	0715-500- 11	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL ALTERNATE SYSTEM, CONVENTIONAL	EA	10.000
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,739.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	5,790.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	6.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	181.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	820.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	3.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	27.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	2.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	1.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	2.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	3.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	48.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	26.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	57.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	24.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	10.000
	0653- 1- 40	PEDESTRIAN SIGNAL, RELOCATE	AS	1.000

Call Order: 007 Proposal: T6505

ALT	Item	Description	Unit	Quantity
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	4.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	5.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	39.000
	0660- 4- 42	VEHICLE DETECTION SYSTEM- VIDEO, RELOCATE ABOVE GROUND EQUIPMENT	EA	12.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	46.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	14.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	6.000
	0682- 1-600	ITS CCTV CAMERA,, REMOVE & DISPOSAL	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3.000
Section 0005 Landscape / Peripheral				
	0581- 1- 2	RELOCATE TREES AND PALMS, PALM, >=14' OF CLEAR TRUNK	EA	24.000
	0581- 1- 7	RELOCATE TREES AND PALMS,PALMS, <14' OF CLEAR TRUNK, SABAL PALM ONLY	EA	2.000
Section 0006 Utilities				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43326435601)	LS	1.000
	1060- 15-	UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	EA	5.000
	1080- 24-500	UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	EA	36.000