

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT200226 Call Order: 005 Proposal: T3725 District:03  
 Counties: OKALOOSA  
 Road Name: SR 189  
 Limits: FROM SR 4 TO THE ALABAMA ST LINE  
 Project(s): 43627315201(\*) Federal Aid No: D319097B  
 Total Roadway Length: 14.260 Miles Contract Days: 255  
 Total Bridge Length: 0.038 Miles Letting Date: 02/26/20  
 Total Proposal Length: 14.298 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 Day Standard

Proposal Budget Estimate: \$7,344,263.00

Please read the full advertisement

Description:

The improvements under this contract consist of FPID 436273-1-52-01 (SR 189 from SR 4 to Alabama State Line) which includes milling and resurfacing, northbound left turn lane widening at Red Barrow Road, southbound left turn lane widening at CR 2A. All widening is within right of way, minor drainage, signing and pavement markings, expansion joint repair for Bridge No.'s 570093 and 570092 and base work. All work is in Okaloosa County.

**Call Order: 005 Proposal: T3725**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43627315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43627315201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	604.000
	0102- 60-	WORK ZONE SIGN	ED	16,575.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	32,186.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	3,233.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	524.000
	0104- 10- 3	SEDIMENT BARRIER	LF	16,264.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	257.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	66.000
	0107- 1-	LITTER REMOVAL	AC	1,193.400
	0107- 2-	MOWING	AC	994.500
	0110- 1- 1	CLEARING & GRUBBING (43627315201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	8.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,835.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43627315201)	LS	1.000
	0285-707-	OPTIONAL BASE, BASE GROUP 07	SY	1,304.000
	0285-744-	OPTIONAL BASE- GRADED AGGREGATE, 15" FOR PROJECT 436273-1-52-01	SY	3,735.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	277.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	198,606.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	17,191.300
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	23,862.500

**Call Order: 005 Proposal: T3725**

ALT	Item	Description	Unit	Quantity
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	80.500
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	4.000
	0425- 1-511	INLETS, DT BOT, TYPE B, <10'	EA	5.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	1.000
	0425- 1-555	INLETS, DT BOT, TYPE E, PARTIAL	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	2.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	2.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	56.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	8.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	542.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	601.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	27.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	4.000
	0432- 3- 2	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 18"	EA	3.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	176.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	36.900
	0524- 1- 3	CONCRETE DITCH PAVEMENT, NON REINFORCED, 5"	SY	30.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	2.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	8.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,546.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	12.000
	0536- 73-	GUARDRAIL REMOVAL	LF	2,137.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	19.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	39,996.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	28.566
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	428.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	12.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	14.418
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	275.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	9.414
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43627315201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	38.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	9.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	39.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	26.851
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	8.963
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43627315201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	428.000

**Call Order: 005 Proposal: T3725**

ALT	Item	Description	Unit	Quantity
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	12.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	275.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	2.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.715
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.455
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	9.414
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.104
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.052
	0713-103-231	PERMANENT TAPE, YELLOW, 10-30 SKIP/ 3-9 DOTTED, 6" FOR CONCRETE SURFACES	GM	0.029