

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT200226 Call Order: 008 Proposal: T4534 District:04
 Counties: BROWARD
 Road Name: ROCK ISLAND RD
 Limits: FROM W SAMPLE RD TO WILES RD
 Project(s): 43654115201(*) Federal Aid No: D420002B
 Total Roadway Length: 1.024 Miles Contract Days: 167
 Total Bridge Length: 0.000 Miles Letting Date: 02/26/20
 Total Proposal Length: 1.024 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Calendar Days

Proposal Budget Estimate: \$1,378,994.00

Please read the full advertisement

Description:

The improvements under this contract consist of but are not limited to the construction of 5-foot bicycle lanes on northbound and southbound directions of Rock Island Rd. The bicycle lanes are achieved by a combination of 3-foot of widening and narrowing of travel lanes.

Call Order: 008 Proposal: T4534

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43654115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43654115201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	400.000
	0102- 60-	WORK ZONE SIGN	ED	13,527.000
	0102- 61-	BUSINESS SIGN	EA	2.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	25,050.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	3,340.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	389.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	334.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	362.000
	0104- 10- 3	SEDIMENT BARRIER	LF	9,519.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	25.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43654115201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43654115201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.290
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	38.000
	0120- 1-	REGULAR EXCAVATION	CY	2,418.000
	0120- 6-	EMBANKMENT	CY	193.000
	0160- 4-	TYPE B STABILIZATION	SY	4,186.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	3,574.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	21,072.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	265.000

Call Order: 008 Proposal: T4534

ALT	Item	Description	Unit	Quantity
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	1,351.900
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	74.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	5,186.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	227.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	63.000
	0527- 2-	DETECTABLE WARNINGS	SF	404.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	11,044.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43654115201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	33.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	9.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	32.000
	0700- 12- 22	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, TWO BEACONS	AS	1.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	180.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43654115201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	581.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	360.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.572
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	13.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	19.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.015
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	303.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	23.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	23.000
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	1.803
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.698
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.030
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.383
	0920-711- 10	GREEN COLORED PAVEMENT MARKING, BIKE LANE, PROJECT 436541-1-52-01	SF	1,623.000