

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT200226	Call Order: 014	Proposal: T6472	District:06
Counties:	MIAMI-DADE			
Road Name:	SR 90/SW 8TH ST			
Limits:	AT SW 157 AVE			
Project(s):	44167015201(*)	Federal Aid No: D619037B		
Project(s):	44167015202	Federal Aid No: N/A		
Total Roadway Length:	0.584 Miles	Contract Days:	200	
Total Bridge Length:	0.000 Miles	Letting Date:	02/26/20	
Total Proposal Length:	0.584 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Calendar Days	
Proposal Budget Estimate:	\$1,201,401.00			

Please read the full advertisement

Description: FLEXIBLE START

The improvements under this contract consist of Intersection Improvement along SR 90/SW 8 St.

Call Order: 014 Proposal: T6472

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44167015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44167015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	10,050.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	29,950.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	600.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	642.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,486.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	8.000
	0107- 1-	LITTER REMOVAL	AC	30.730
	0107- 2-	MOWING	AC	21.260
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44167015201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44167015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	176.000
	0120- 1-	REGULAR EXCAVATION	CY	2,221.000
	0120- 6-	EMBANKMENT	CY	878.000
	0160- 4-	TYPE B STABILIZATION	SY	5,066.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	493.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	4,569.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	236.000
	0327- 70- 13	MILLING EXIST ASPH PAVT, 1 3/4" AVG DEPTH	SY	12,491.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1,944.400
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	648.400
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	76.100
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	7.000

Call Order: 014 Proposal: T6472

ALT	Item	Description	Unit	Quantity
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	1.000
	0425- 1-545	INLETS, DITCH BOTTOM, TYPE D, PARTIAL	EA	3.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	2.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	1,245.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	46.000
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	133.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	1.000
	0443- 70- 4	FRENCH DRAIN, 24"	LF	116.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	1,381.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	57.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	57.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	154.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	45.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,002.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	135.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44167015201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44167015202)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	10.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	8.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0701- 18-101	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6"	GM	0.470
	0701- 18-201	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.248
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	182.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44167015201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44167015202)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	153.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	26.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.282
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	9.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	8.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	8.000

Call Order: 014 Proposal: T6472

ALT	Item	Description	Unit	Quantity
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.377
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.292
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.914
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.479