

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT200226 Call Order: 015 Proposal: T6478 District:06
Counties: MIAMI-DADE
Road Name: SR 826/NW/NE 167TH ST
Limits: AT NORTH MIAMI AVE
Project(s): 44030415201(*) Federal Aid No: D619051B
Project(s): 44030415202 Federal Aid No: D619051B
Project(s): 44030415203 Federal Aid No: D619051B
Total Roadway Length: 0.110 Miles Contract Days: 140
Total Bridge Length: 0.000 Miles Letting Date: 02/26/20
Total Proposal Length: 0.110 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 120 Calendar Days
Proposal Budget Estimate: \$434,618.00

Please read the full advertisement

Description: FLEXIBLE START

The improvements under this contract consist of Intersection Improvement along SR 826/NW/NE 167th St.

Call Order: 015 Proposal: T6478

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44030415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44030415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	416.000
	0102- 60-	WORK ZONE SIGN	ED	6,065.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,070.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	380.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	37.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	225.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	331.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	140.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	140.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	8.000
	0107- 1-	LITTER REMOVAL	AC	1.400
	0107- 2-	MOWING	AC	0.030
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44030415201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44030415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44030415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44030415203)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	174.000
	0120- 1-	REGULAR EXCAVATION	CY	65.100
	0160- 4-	TYPE B STABILIZATION	SY	67.000

Call Order: 015 Proposal: T6478

ALT	Item	Description	Unit	Quantity
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	67.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	1,165.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	32.600
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	67.900
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	107.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	187.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	23.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	76.000
	0527- 2-	DETECTABLE WARNINGS	SF	56.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	37.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.044
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44030415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44030415202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44030415203)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44030415201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44030415203)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	128.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	35.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.031
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	7.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	13.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.078
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	0.042
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.165
Section 0003 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	330.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,146.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	2.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	2.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	1.000
	0715-500- 11	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL ALTERNATE SYSTEM, CONVENTIONAL	EA	2.000

Call Order: 015 Proposal: T6478

ALT	Item	Description	Unit	Quantity
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	295.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	285.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	17.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	2.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	1.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	1.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 25- 10	STEEL MAST ARM ASSEMBLY, REPLACE ARM ON EXISTING POLE, 6	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	8.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	2.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	2.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	2.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	7.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	1.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000