

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT200129 Call Order: 006 Proposal: T3732 District:03  
 Counties: ESCAMBIA  
 Road Name: SR 10A (US 90)  
 Limits: AT SR 295 (NEW WARRINGTON RD) INTERSECTION  
 Project(s): 44172515201(\*) Federal Aid No: D319118B  
 Total Roadway Length: 0.095 Miles Contract Days: 90  
 Total Bridge Length: 0.000 Miles Letting Date: 01/29/20  
 Total Proposal Length: 0.095 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 Day Standard

Proposal Budget Estimate: \$567,086.00

Please read the full advertisement

**Description:**

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at:  
<https://www.fdot.gov/equalopportunity/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at:  
<http://www.cmdp-bgp.com/bdi-projects.html>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at:  
<https://www.fdot.gov/equalopportunity/bdi.shtm>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: [fdot.bdi@dot.state.fl.us](mailto:fdot.bdi@dot.state.fl.us).

All Sublet work must be contracted to a small business or businesses as defined by the Department. The subcontractor must also submit a notarized Small Business Affidavit Form provided by the Department prior to the start of work.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the project's major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the Expedite application.

BDI Reference Sheet may be found at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

The improvements under this contract consist of base work, milling and resurfacing, drainage improvements, signing and pavement markings, signal improvements, and other incidental construction for the SR 10A (US 90) Mobile Hwy at SR 295 New Warrington Road intersection safety improvements in Escambia County from MP 11.636 to MP 11.731.

**Call Order: 006 Proposal: T3732**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44172515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44172515201)	LS	1.000

**Call Order: 006 Proposal: T3732**

ALT	Item	Description	Unit	Quantity
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (44172515201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	96.000
	0102- 60-	WORK ZONE SIGN	ED	2,970.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,754.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	150.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	664.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	85.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	272.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	90.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	90.000
	0104- 10- 3	SEDIMENT BARRIER	LF	515.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000
	0107- 1-	LITTER REMOVAL	AC	4.420
	0107- 2-	MOWING	AC	1.870
	0110- 1- 1	CLEARING & GRUBBING (44172515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	538.000
	0120- 1-	REGULAR EXCAVATION	CY	609.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	112.500
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	480.000
	0327- 70- 12	MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH	SY	4,073.000
	0327- 70- 13	MILLING EXIST ASPH PAVT, 1 3/4" AVG DEPTH	SY	217.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	18.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	34.400
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	327.900
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	2.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	2.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	2.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	52.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	32.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	14.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	662.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	17.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	85.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	224.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	139.000
	0527- 2-	DETECTABLE WARNINGS	SF	96.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,739.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44172515201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	3.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	5.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44172515201)	LS	1.000

**Call Order: 006 Proposal: T3732**

ALT	Item	Description	Unit	Quantity
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	509.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	138.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	7.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	97.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	186.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.360
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.125
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.252
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	205.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	383.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	15.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	83.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	9.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	9.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	1.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	6.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	8.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	2.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000
	0660- 4- 60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	2.000
	0670- 5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000

**Call Order: 006 Proposal: T3732**

ALT	Item	Description	Unit	Quantity
	0684- 6- 12	WIRELESS COMMUNICATION DEVICE, FURNISH & INSTALL ETHERNET SUBSCRIBER UNIT	EA	1.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	3.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000