

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT200129 Call Order: 007 Proposal: T3744 District:03
Counties: JACKSON
Road Name: SR 273 (CAMPBELLTON HWY)
Limits: FROM WASHINGTON CO LINE TO SR 75 (US 231)
Project(s): 43972415201(*) Federal Aid No: D319171B
Total Roadway Length: 10.687 Miles Contract Days: 180
Total Bridge Length: 0.000 Miles Letting Date: 01/29/20
Total Proposal Length: 10.687 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 15 Day Standard
Proposal Budget Estimate: \$5,639,924.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing. Other incidental work including minor drainage improvements and signing and pavement marking on SR 273 Campbellton Hwy from Washington Co. Line to SR 75 (US 231) in Jackson County.

Call Order: 007 Proposal: T3744

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43972415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43972415201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	412.000
	0102- 60-	WORK ZONE SIGN	ED	8,820.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	45,624.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	7,884.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	762.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	360.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	360.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,228.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	170.000
	0107- 1-	LITTER REMOVAL	AC	579.680
	0107- 2-	MOWING	AC	498.950
	0110- 1- 1	CLEARING & GRUBBING (43972415201)	LS	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	3,464.600
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43972415201)	LS	1.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	474.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	148,261.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	1,557.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	20,548.800
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	14,748.700
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	16.100
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	16.000

Call Order: 007 Proposal: T3744

ALT	Item	Description	Unit	Quantity
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	132.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	8.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	20.000
	0430-174-215	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 15"SD	LF	60.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	16.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	16.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	8.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	2.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	2.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	17.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	4.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	2.000
	0430-984-623	MITERED END SECTION, OPTIONAL OTHER - ELLIP/ARCH, 15" SD	EA	2.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	522.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	189.300
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	8.000
	0546- 71- 2	RAISED RUMBLE STRIP SET- SHORT TERM	EA	8.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	42,777.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	42.096
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	278.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.132
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	43.986
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	20.271
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43972415201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	5.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	3.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	20.397
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	10.060
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43972415201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	139.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.066
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.651
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.084
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	6.757