

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT200129	Call Order: 008	Proposal: T4514	District:04
Counties:	BROWARD			
Road Name:	POMPANO BEACH MOBILITY SIDEWALKS			
Limits:	ALONG NE 6TH ST, NE 4TH ST AND SW 6TH ST			
Project(s):	43778515201(*)	Federal Aid No: D419068B		
Total Roadway Length:	0.426 Miles	Contract Days:	131	
Total Bridge Length:	0.000 Miles	Letting Date:	01/29/20	
Total Proposal Length:	0.426 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Calendar Days	
Proposal Budget Estimate:	\$316,296.00			

Please read the full advertisement

Description:

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a Small Business as defined by FDOT. Small business size standards can be found at: <http://www.fdot.gov/equalopportunity/bdi.shtm>

For more information about bidding on BDI projects, please see the training guide located at <http://www.cmdp-bgp.com/bdi-projects.html>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at:

<https://www.fdot.gov/equalopportunity/bdi.shtm>

Send a completed and notarized affidavit as an attachment to: fdot.bdi@dot.state.fl.us.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the proposal's major work type, per Rule 14-22, Florida Administrative Code.

Please upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the File Attachment Upload tab in the AASHTOWare Project Bids application.

BDI Reference Sheet may be found at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

The improvements under this contract consist of pedestrian sidewalk connectivity along 3 local roads within the City of Pompano Beach.

Call Order: 008 Proposal: T4514

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43778515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43778515201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,518.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	10,253.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	126.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	3.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	624.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,638.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	16.000
	0110- 1- 1	CLEARING & GRUBBING (43778515201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.030
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	238.000
	0120- 1-	REGULAR EXCAVATION	CY	357.000
	0120- 6-	EMBANKMENT	CY	45.600
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,369.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	75.300
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	15.500
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	1.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	20.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	141.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	288.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	29.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	980.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	621.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	84.000
	0527- 2-	DETECTABLE WARNINGS	SF	403.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,151.000
	0591- 1- 98	IRRIGATION SLEEVE, 4" DIAMETER, PROJECT NUMBER 437785-1-52-01	LF	270.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43778515201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	5.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	14.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43778515201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	153.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	618.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	320.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.059
Section 0003 Signalization				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	8.000