

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT200129 Call Order: 009 Proposal: T4535 District:04  
 Counties: BROWARD  
 Road Name: OLD GRIFFIN RD  
 Limits: FROM SR 818 (GRIFFIN RD) TO OCEAN WATERWAY BLVD  
 Project(s): 43654415201(\*) Federal Aid No: D419055B  
 Total Roadway Length: 0.315 Miles Contract Days: 177  
 Total Bridge Length: 0.000 Miles Letting Date: 01/29/20  
 Total Proposal Length: 0.315 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 60 Calendar Days

Proposal Budget Estimate: \$961,026.00

Please read the full advertisement

**Description:**

The improvements under this contract consist of, but not limited to, milling and resurfacing, widening, drainage improvements (inlets, pipes, french drains), patterned pavement (green bike lanes), signing, pavement markings (paint and thermoplastic), lighting (light poles, pull boxes, conductors, conduit), excavation and embankment, sod, and monitoring existing structures (inspection and settlement, vibration).

**Call Order: 009 Proposal: T4535**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43654415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43654415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	4,426.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	2,450.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	2,450.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,310.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	224.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	170.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	82.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	200.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	438.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.200
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.200
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.200
	0104- 10- 3	SEDIMENT BARRIER	LF	3,004.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,133.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	6.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43654415201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43654415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43654415201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.590

**Call Order: 009 Proposal: T4535**

ALT	Item	Description	Unit	Quantity
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	106.000
	0120- 1-	REGULAR EXCAVATION	CY	304.000
	0120- 4-	SUBSOIL EXCAVATION	CY	432.000
	0120- 6-	EMBANKMENT	CY	1,019.000
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	425.000
	0160- 4-	TYPE B STABILIZATION	SY	1,510.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	1,309.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	412.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	4,706.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	614.700
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	523.100
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	2.000
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	6.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	22.000
	0443- 70- 4	FRENCH DRAIN, 24"	LF	110.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	406.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,011.000
	0527- 2-	DETECTABLE WARNINGS	SF	10.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,029.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.500
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.200
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.300
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43654415201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	18.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43654415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	52.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	495.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	24.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.033
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	184.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	55.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	11.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	11.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.024

**Call Order: 009 Proposal: T4535**

ALT	Item	Description	Unit	Quantity
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.055
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.610
	0920-711- 1	GREEN COLORED PAVEMENT MARKING, BIKE LANE, PROJECT 436544-1-52-01	SF	1,602.000
<b>Section 0003 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	252.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	948.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	900.000
	0715- 4- 15	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT	EA	2.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	2.000