

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT200129	Call Order: 010	Proposal: T4536	District:04
Counties:	PALM BEACH			
Road Name:	SWINTON AVE			
Limits:	FROM S 10TH ST TO NE 4TH ST/LAKE IDA RD			
Project(s):	43838915201(*)	Federal Aid No:	D419043B	
Total Roadway Length:	1.517 Miles	Contract Days:	274	
Total Bridge Length:	0.000 Miles	Letting Date:	01/29/20	
Total Proposal Length:	1.517 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Calendar Days	

Proposal Budget Estimate: \$1,494,495.00

Please read the full advertisement

Description:

The improvements under this contract consist of, but not limited to, milling and resurfacing, curb and gutter, concrete sidewalk and driveways, detectable warnings, drainage, signing and pavement markings, signalization for vehicular detection, and structure monitoring along Swinton Ave.

Call Order: 010 Proposal: T4536

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43838915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43838915201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	82.500
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	24.000
	0102- 60-	WORK ZONE SIGN	ED	20,672.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,512.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	1,272.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	9,234.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,600.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	804.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	248.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,488.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,918.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,918.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,501.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	20.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43838915201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43838915201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43838915201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.120

Call Order: 010 Proposal: T4536

ALT	Item	Description	Unit	Quantity
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	618.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	13.000
	0120- 1-	REGULAR EXCAVATION	CY	252.700
	0120- 6-	EMBANKMENT	CY	54.500
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	3.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT/DRIVEWAY BASE- ASPHALT MATERIAL	TN	29.600
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	29,498.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	2,281.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	160.100
	0425- 1-481	INLETS, CURB, TYPE 8, <10'	EA	2.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	8.000
	0425- 1-535	INLETS, DITCH BOTTOM TYPE C MODIFIED- BACK OF SIDEWALK, PARTIAL	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	6.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	375.000
	0443- 70- 3	FRENCH DRAIN, 18"	LF	460.000
	0443- 72- 20	FRENCH DRAIN- AGGREGATE WITHOUT PIPE, PROJECT 438389-1-52-01, 2.5' DEPTH	SY	678.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	68.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	968.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,070.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	3.000
	0527- 2-	DETECTABLE WARNINGS	SF	304.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	4,792.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.961
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.117
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43838915201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	51.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	8.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	22.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	1.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	5.000
	0700- 3-502	SIGN PANEL, RELOCATE, 12-20 SF	EA	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43838915201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,349.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	398.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	495.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.050
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	7.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	27.000

Call Order: 010 Proposal: T4536

ALT	Item	Description	Unit	Quantity
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	576.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.024
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	540.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	85.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.198
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.028
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.073
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.891
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.644
Section 0003 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	17.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	6.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	24.000