

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT200129	Call Order: 011	Proposal: T4540	District:04
Counties:	MARTIN			
Road Name:	SR 5 (US 1/ROOSEVELT BR)			
Limits:	FROM SW JOAN JEFFERSON WAY TO NW WRIGHT BLVD			
Project(s):	43834515201(*)	Federal Aid No:	D419087B	
Total Roadway Length:	0.344 Miles	Contract Days:	95	
Total Bridge Length:	0.863 Miles	Letting Date:	01/29/20	
Total Proposal Length:	1.207 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Calendar Days	

Proposal Budget Estimate: \$1,195,073.00

Please read the full advertisement

**Description:**

The improvements under this contract consist of, but not limited to, removal of the existing pavement markings on the bridges, placement of permanent tape markings on the bridges to accommodate 7' buffered bike lanes, milling and resurfacing & restriping of the bridge approaches, upgrade ADA/curb ramps, replace existing crosswalks with high emphasis pavement markings, and replace existing roadway signs along SR 5 (US 1/Roosevelt Br.).

**Call Order: 011 Proposal: T4540**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43834515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43834515201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	32.000
	0102- 60-	WORK ZONE SIGN	ED	6,776.000
	0102- 62-	BARRIER MOUNTED WORK ZONE SIGN- INDEX 11871/700-013	ED	576.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	77,000.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	20.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	380.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	252.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	218.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	72.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	72.000
	0104- 10- 3	SEDIMENT BARRIER	LF	21.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	18.000
	0107- 1-	LITTER REMOVAL	AC	11.280
	0107- 2-	MOWING	AC	3.040
	0110- 1- 1	CLEARING & GRUBBING (43834515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	15.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	22,333.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1,842.500
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	1,228.300
	0425- 5-	MANHOLE, ADJUST	EA	3.000

**Call Order: 011 Proposal: T4540**

ALT	Item	Description	Unit	Quantity
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	19.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	8.000
	0527- 2-	DETECTABLE WARNINGS	SF	25.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	59.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	6.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	6.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.941
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.130
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	957.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	300.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	937.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	4.940
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.900
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.628
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43834515201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	5.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	5.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43834515201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.130
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	957.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	389.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	937.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	19.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	6.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	6.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.941
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	4.940
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.628
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	5.210
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	3.465

**Call Order: 011 Proposal: T4540**

ALT	Item	Description	Unit	Quantity
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.710
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	5.210
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	23,300.000
	0920-711- 5	GREEN COLORED PAVEMENT MARKING, BIKE LANE, PROJECT 438345-1-52-01	SF	1,961.000