

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT200129	Call Order: 016	Proposal: T6499	District:06
Counties:	MIAMI-DADE			
Road Name:	SR 25 (NW 36 ST)			
Limits:	FROM NW 5 AVE TO NORTH MIAMI AVE			
Project(s):	43992215201(*)	Federal Aid No:	D619044B	
Project(s):	43992215601	Federal Aid No:	N/A	
Total Roadway Length:	0.623 Miles	Contract Days:	160	
Total Bridge Length:	0.000 Miles	Letting Date:	01/29/20	
Total Proposal Length:	0.623 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Calendar Days	
Proposal Budget Estimate:	\$603,258.00			

Please read the full advertisement

Description: Flexible Start

The improvements under this contract consist of intersection improvements along SR 25 (NW 36 St.).

Call Order: 016 Proposal: T6499

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43992215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43992215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	28.000
	0102- 60-	WORK ZONE SIGN	ED	6,440.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	17,348.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	848.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	119.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,214.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	480.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	480.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,428.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	33.000
	0107- 1-	LITTER REMOVAL	AC	9.440
	0107- 2-	MOWING	AC	0.910
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43992215201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43992215201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43992215201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	218.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43992215201)	LS	1.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	9,318.000

Call Order: 016 Proposal: T6499

ALT	Item	Description	Unit	Quantity
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	512.500
	0425- 5-	MANHOLE, ADJUST	EA	19.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,235.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	54.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	43.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	139.000
	0527- 2-	DETECTABLE WARNINGS	SF	120.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	322.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.841
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.080
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	46.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.504
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43992215201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	24.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	6.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43992215201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	328.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	734.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	392.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.061
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	20.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	22.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	171.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID, 6"	LF	183.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	830.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	710.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	18.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.030
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.214
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	0.010
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.812
Section 0003 Lighting				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000

Call Order: 016 Proposal: T6499

ALT	Item	Description	Unit	Quantity
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	195.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	126.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	24.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	5.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	1.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	10.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0653- 1- 40	PEDESTRIAN SIGNAL, RELOCATE	AS	1.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	4.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	1.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	7.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	3.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
Section 0005 Utilities				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43992215601)	LS	1.000
	1060- 15-	UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	EA	6.000
	1080- 24-500	UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	EA	14.000