

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT200129	Call Order: 017	Proposal: T6523	District:06
Counties:	MIAMI-DADE			
Road Name:	SR 9 (NW 27TH AVE)			
Limits:	FROM S OF SR 934 (NW 79TH ST) TO N OF SR 932 (NW 103RD ST)			
Project(s):	42918535201(*)	Federal Aid No: D619067B		
Total Roadway Length:	1.621 Miles	Contract Days:	250	
Total Bridge Length:	0.000 Miles	Letting Date:	01/29/20	
Total Proposal Length:	1.621 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Calendar Days	

Proposal Budget Estimate: \$1,680,739.00

Please read the full advertisement

Description: Flexible Start, Incentive / Disincentive

The improvements under this contract consists of drainage improvements along SR 9 (NW 27th Ave.).

Call Order: 017 Proposal: T6523

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (42918535201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42918535201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	28.000
	0102- 60-	WORK ZONE SIGN	ED	18,890.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	432.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	1,044.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	1,584.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	8,028.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	12,975.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	2,990.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	540.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	385.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	42.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	583.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	250.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	250.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	150.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	52.000
	0107- 1-	LITTER REMOVAL	AC	48.810
	0107- 2-	MOWING	AC	15.310
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (42918535201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (42918535201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,692.000
	0120- 1-	REGULAR EXCAVATION	CY	193.700

Call Order: 017 Proposal: T6523

ALT	Item	Description	Unit	Quantity
	0160- 4-	TYPE B STABILIZATION	SY	496.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	496.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	11,474.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	37.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	649.600
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	4.000
	0425- 1-203	INLETS, CURB, TYPE 9, J BOT, <10'	EA	1.000
	0425- 1-205	INLETS, CURB, TYPE 9, PARTIAL	EA	1.000
	0425- 1-322	INLETS, CURB, TYPE P-2, >10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	12.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	20.000
	0425- 1-362	INLETS, CURB, TYPE P-6, >10'	EA	1.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	1.000
	0425- 1-369	INLETS, CURB, TYPE P-6, MODIFY	EA	1.000
	0425- 1-561	INLETS, DT BOT, TYPE F, <10'	EA	2.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	11.000
	0425- 2- 42	MANHOLES, P-7, >10'	EA	2.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	2.000
	0425- 2- 72	MANHOLES, J-7, >10'	EA	1.000
	0425- 3- 91	JUNCTION BOX, DRAINAGE, UTILITY, < 10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	6.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	1.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	40.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	8.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	2,106.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	8.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	16.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	4,345.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	80.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	99.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	20.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,527.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,151.000
	0527- 2-	DETECTABLE WARNINGS	SF	267.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,592.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42918535201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	24.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	3.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	3.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42918535201)	LS	1.000

Call Order: 017 Proposal: T6523

ALT	Item	Description	Unit	Quantity
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	953.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	146.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	247.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.193
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	3.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	47.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	190.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	12.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	9.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.241
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.145
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.512
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.566
Section 0003 Lighting				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	545.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	1,315.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	19.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	105.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	3.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	3.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	2.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	4.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000