

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT200729	Call Order: 006	Proposal: T2776	District:02
Counties:	COLUMBIA			
Road Name:	SR 20			
Limits:	FROM BLUE JAY CT TO DRUMMOND COMMUNITY BANK			
Project(s):	43399315201(*)	Federal Aid No:	D217168B	
Total Roadway Length:	0.572 Miles	Contract Days:	75	
Total Bridge Length:	0.000 Miles	Letting Date:	07/29/20	
Total Proposal Length:	0.572 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days (Acq. time)	
Proposal Budget Estimate:	\$206,923.00			

Please read the full advertisement

Description:

The improvements under this contract consist of sidewalk, with minor drainage improvements and other incidental construction on SR 20, from Blue Jay Ct. to Drummond Community Bank in Columbia County.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 006 Proposal: T2776

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43399315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43399315201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	825.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,575.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	900.000
	0104- 10- 3	SEDIMENT BARRIER	LF	971.000
	0107- 1-	LITTER REMOVAL	AC	9.190
	0107- 2-	MOWING	AC	7.490
	0110- 1- 1	CLEARING & GRUBBING (43399315201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	26.000
	0120- 1-	REGULAR EXCAVATION	CY	183.000
	0120- 6-	EMBANKMENT	CY	414.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	80.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	106.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	60.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	4.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	4.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,469.000
	0527- 2-	DETECTABLE WARNINGS	SF	188.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	5,139.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43399315201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	3.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	3.000
	0706- 1- 1	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS	EA	24.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	536.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	83.000
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.052