

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

| | | | | |
|------------------------|----------------------------|----------------------------|---------------------|-------------|
| Letting: | CT200729 | Call Order: 007 | Proposal: T2777 | District:02 |
| Counties: | ALACHUA | | | |
| Road Name: | SR 26 | | | |
| Limits: | FROM SR 45 TO CR 241 SOUTH | | | |
| Project(s): | 44126215201(*) | Federal Aid No: | D220101B | |
| Total Roadway Length: | 4.870 Miles | Contract Days: | 180 | |
| Total Bridge Length: | 0.000 Miles | Letting Date: | 07/29/20 | |
| Total Proposal Length: | 4.870 Miles | Contract Execution Days: | 10 | |
| | | Special Start Date: | N/A | |
| | | Aquis/Flexible Start Time: | 15 Days (Acq. time) | |

Proposal Budget Estimate: \$4,466,071.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, curb and gutter, traffic signals, highway signing, sidewalks/bicycle path, and other incidental construction on SR 26 from SR 45 to CR 241 South in Alachua County.

Call Order: 007 Proposal: T2777

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|-------------|---|------|------------|
| Section 0001 Roadway | | | | |
| | 0101- 1- | MOBILIZATION (44126215201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (44126215201) | LS | 1.000 |
| | 0102- 14- | TRAFFIC CONTROL OFFICER | HR | 48.000 |
| | 0102- 60- | WORK ZONE SIGN | ED | 9,720.000 |
| | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED | 18,720.000 |
| | 0102- 74- 8 | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) | FD | 9,046.000 |
| | 0102- 76- | ARROW BOARD / ADVANCE WARNING ARROW PANEL | ED | 360.000 |
| | 0102- 78- | TEMPORARY RETROREFLECTIVE PAVEMENT MARKER | EA | 6,948.000 |
| | 0102- 99- | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY | ED | 900.000 |
| | 0102-104- | TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION | ED | 180.000 |
| | 0102-107- 1 | TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION | ED | 180.000 |
| | 0102-150- 1 | PORTABLE REGULATORY, SIGN | ED | 360.000 |
| | 0102-150- 2 | RADAR SPEED DISPLAY UNIT | ED | 360.000 |
| | 0102-909- | TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS | DA | 180.000 |
| | 0104- 1- | ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS | SY | 14.000 |
| | 0104- 18- | INLET PROTECTION SYSTEM | EA | 70.000 |
| | 0107- 1- | LITTER REMOVAL | AC | 61.930 |
| | 0107- 2- | MOWING | AC | 56.780 |
| | 0108- 1- | MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44126215201) | LS | 1.000 |
| | 0110- 1- 1 | CLEARING & GRUBBING (44126215201) | LS | 1.000 |
| | 0110- 4- 10 | REMOVAL OF EXISTING CONCRETE | SY | 644.000 |
| | 0110- 7- 1 | MAILBOX, F&I SINGLE | EA | 46.000 |

Call Order: 007 Proposal: T2777

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|--------------|--|------|------------|
| | 0120- 2- 2 | BORROW EXCAVATION, TRUCK MEASURE | CY | 866.700 |
| | 0120- 71- | REGULAR EXCAVATION (3-R PROJECTS ONLY) (44126215201) | LS | 1.000 |
| | 0160- 4- | TYPE B STABILIZATION | SY | 542.000 |
| | 0285-701- | OPTIONAL BASE, BASE GROUP 01 | SY | 839.000 |
| | 0285-709- | OPTIONAL BASE, BASE GROUP 09 | SY | 496.000 |
| | 0327- 70- 6 | MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH | SY | 80,996.000 |
| | 0327- 70- 11 | MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH | SY | 52,039.000 |
| | 0327- 70- 19 | MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH | SY | 26,251.000 |
| | 0327- 70- 20 | MILLING EXIST ASPH PAVT, 3 3/4" AVG DEPTH | SY | 52,054.000 |
| | 0334- 1- 13 | SUPERPAVE ASPHALTIC CONC, TRAFFIC C | TN | 4,294.400 |
| | 0334- 1- 53 | SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22 | TN | 10,179.900 |
| | 0337- 7- 25 | ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22 | TN | 5,213.200 |
| | 0337- 7- 83 | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22 | TN | 4,717.500 |
| | 0425- 5- | MANHOLE, ADJUST | EA | 1.000 |
| | 0425- 82- | REPLACE GRATE | EA | 2.000 |
| | 0430-984-125 | MITERED END SECTION, OPTIONAL ROUND, 18" SD | EA | 1.000 |
| | 0430-984-625 | MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD | EA | 6.000 |
| | 0520- 1- 10 | CONCRETE CURB & GUTTER, TYPE F | LF | 781.000 |
| | 0522- 1- | CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK | SY | 85.000 |
| | 0522- 2- | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK | SY | 328.000 |
| | 0527- 2- | DETECTABLE WARNINGS | SF | 604.000 |
| | 0570- 1- 2 | PERFORMANCE TURF, SOD | SY | 1,459.000 |
| | 0710- 11-101 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6" | GM | 34.605 |
| | 0710- 11-102 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8" | GM | 0.102 |
| | 0710- 11-123 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12" | LF | 6,882.000 |
| | 0710- 11-125 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24" | LF | 2,076.000 |
| | 0710- 11-131 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE | GM | 30.009 |
| | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6" | GM | 28.593 |
| | 0710- 11-231 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6" | GM | 2.271 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44126215201) | LS | 1.000 |
| Section 0002 Signing | | | | |
| | 0546- 72- 3 | GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL | GM | 6.758 |
| | 0700- 1- 11 | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF | AS | 3.000 |
| | 0701- 18-101 | PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6" | GM | 1.221 |
| | 0701- 18-201 | PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SOLID, 6" | GM | 0.820 |
| | 0710- 90- | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44126215201) | LS | 1.000 |
| | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT | LF | 2,294.000 |
| | 0711- 11-124 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS | LF | 105.000 |

Call Order: 007 Proposal: T2777

| ALT | Item | Description | Unit | Quantity |
|-----------------------------------|--------------|--|------|----------|
| | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK | LF | 692.000 |
| | 0711- 11-141 | THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" | GM | 0.426 |
| | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL | EA | 2.000 |
| | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW | EA | 151.000 |
| | 0711- 11-224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON | LF | 337.000 |
| | 0711- 11-241 | THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6" | GM | 1.119 |
| | 0711- 14-125 | THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK | LF | 540.000 |
| | 0711- 14-160 | THERMOPLASTIC, PREFORMED, WHITE, MESSAGE | EA | 39.000 |
| | 0711- 14-170 | THERMOPLASTIC, PREFORMED, WHITE, ARROW | EA | 39.000 |
| | 0711- 15-101 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6" | GM | 7.137 |
| | 0711- 15-131 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP | GM | 7.692 |
| | 0711- 15-201 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6" | GM | 5.326 |
| | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" | GM | 3.248 |
| | 0711- 16-102 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8" | GM | 0.034 |
| | 0711- 16-131 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP | GM | 2.311 |
| | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" | GM | 3.474 |
| | 0711- 16-231 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6" | GM | 0.757 |
| Section 0003 Lighting | | | | |
| | 0635- 2- 11 | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE | EA | 2.000 |
| | 0715- 4- 12 | LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT | EA | 2.000 |
| | 0715- 5- 31 | LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE | EA | 3.000 |
| | 0715-500- 1 | POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL | EA | 2.000 |
| Section 0004 Signalization | | | | |
| | 0660- 2-103 | LOOP ASSEMBLY, F&I, TYPE C | AS | 13.000 |
| | 0665- 1- 11 | PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD | EA | 1.000 |
| | 0665- 1- 60 | PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN | EA | 1.000 |