

Call Order: 008 Proposal: T2779

ALT	Item	Description	Unit	Quantity
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43949015201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43949015201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.590
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	4,903.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	11.000
	0120- 1-	REGULAR EXCAVATION	CY	6,734.000
	0120- 4-	SUBSOIL EXCAVATION	CY	4,215.000
	0120- 6-	EMBANKMENT	CY	14,831.000
	0160- 4-	TYPE B STABILIZATION	SY	29,909.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	8,492.000
	0285-705-	OPTIONAL BASE, BASE GROUP 05	SY	14,031.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	1,667.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	23,194.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	2,015.600
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	3,814.800
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	487.100
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	65.400
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	11,736.000
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	2.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	3.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	16.000
	0425- 1-531	INLETS, DITCH BOTTOM, TYPE C MODIFIED- BACK OF SIDEWALK, <10'	EA	3.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	32.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	2.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	1.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	2.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	3.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	7.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	2.000
	0425- 3- 41	JUNCTION BOX, DRAINAGE, P-7, <10'	EA	1.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	10.000
	0425- 6-	VALVE BOXES, ADJUST	EA	40.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	349.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	13.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	104.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	4,574.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	3,903.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	599.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	11.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	910.000

Call Order: 008 Proposal: T2779

ALT	Item	Description	Unit	Quantity
	0430-518-100	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND	EA	5.000
	0430-536-100	STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	5.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	3.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	5.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	14.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	1.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	8.000
	0431- 1-260	PIPE LINING FOR 72" CMP, PROJECT 439490-1-52-01	LF	12.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	1,778.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	9.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	3,088.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	26.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	110.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	90.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	8,836.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	494.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	197.000
	0527- 2-	DETECTABLE WARNINGS	SF	873.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	22.900
	0536- 73-	GUARDRAIL REMOVAL	LF	730.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	48,271.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	62.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43949015201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	62.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	6.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	24.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	49.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	1.000
	0700- 12- 11	SIGN BEACON, F&I GROUND MOUNT- AC POWERED, ONE BEACON	AS	1.000
	0700- 12- 21	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, ONE BEACON	AS	1.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	39.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	28.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43949015201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,596.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	451.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.545
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000

Call Order: 008 Proposal: T2779

ALT	Item	Description	Unit	Quantity
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	72.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,556.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	137.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	20.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	19.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.311
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.116
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.430
Section 0003 Intelligent Transportation System				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	184.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	409.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	30.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	628.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0646- 2-120	ALUMINUM POLE- INDEX 17900/695-001, FURNISH & INSTALL, 20'	EA	1.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	1.000