

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT200729 Call Order: 011 Proposal: T2784 District:02

Counties: SUWANNEE

Road Name: SR 8 (I-10)

Limits: FROM MADISON CO LINE TO US 90

Project(s): 44133715201(*) Federal Aid No: D220103B

Total Roadway Length:	5.861 Miles	Contract Days:	200
Total Bridge Length:	0.000 Miles	Letting Date:	07/29/20
Total Proposal Length:	5.861 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$9,373,717.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, traffic signals, and other incidental construction on SR 8 (I-10) in Suwannee County from Madison County Line to US 90.

Call Order: 011 Proposal: T2784

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	86.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44133715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44133715201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	6,000.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	57,000.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	400.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	5,769.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	800.000
	0102-115-	TYPE III BARRICADE	ED	800.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	400.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	400.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	5,671.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,828.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	41.000
	0107- 1-	LITTER REMOVAL	AC	1,294.360
	0107- 2-	MOWING	AC	1,152.540
	0110- 1- 1	CLEARING & GRUBBING (44133715201)	LS	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	4,051.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44133715201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	618.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	482.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	95,212.000
	0327- 70- 20	MILLING EXIST ASPH PAVT, 3 3/4" AVG DEPTH	SY	171,215.000
	0327- 70- 21	MILLING EXIST ASPH PAVT, 7" AVG DEPTH	SY	21,600.000

Call Order: 011 Proposal: T2784

ALT	Item	Description	Unit	Quantity
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	41,662.800
	0334- 1- 58	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, HIGH POLYMER	TN	6,559.700
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	7,089.200
	0337- 7- 94	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC D, FC-12.5, HIGH POLYMER	TN	1,820.400
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	112.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	114.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	24.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	16.000
	0430-518-100	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND	EA	14.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	13.000
	0430-530-100	STRAIGHT CONCRETE ENDWALLS, 30", SINGLE, 0 DEGREES, ROUND	EA	3.000
	0430-536-100	STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	22.672
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	27,861.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	34,871.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	26.102
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	0.972
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	256.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	128.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	36.117
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.460
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.406
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	26.162
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44133715201)	LS	1.000
Section 0003 Signing				
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44133715201)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.486
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	128.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	64.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.203
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	77.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	12.213

Call Order: 011 Proposal: T2784

ALT	Item	Description	Unit	Quantity
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	12.039
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	12.167
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.838
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.230
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.914
Section 0004 Signalization				
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000