

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT200729	Call Order: 014	Proposal: T3717	District:03
Counties:	WASHINGTON			
Road Name:	CR 278 (PIONEER RD)			
Limits:	OVER PINEY BRANCH (EXISTING BR NO. 610020)			
Project(s):	43720215201(*)	Federal Aid No: D320026B		
Total Roadway Length:	0.184 Miles	Contract Days:	150	
Total Bridge Length:	0.005 Miles	Letting Date:	07/29/20	
Total Proposal Length:	0.189 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	Standard 15 Days	

Proposal Budget Estimate: \$775,730.00

Please read the full advertisement

Description:

The improvements under this contract consist of remove existing Bridge No. 610020 and construct new Box Culvert Bridge No. 614169 on CR 278 Pioneer Road over Piney Branch in Washington County. Other incidental work includes but is not limited to; mill and resurface, signing and pavement marking.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 014 Proposal: T3717

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43720215201)	LS	1.000
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	163.500
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	27,880.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	49.100
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43720215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43720215201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43720215201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43720215201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	39.300
	0102- 60-	WORK ZONE SIGN	ED	2,940.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	72.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	9,858.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	192.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	314.000
	0102-115-	TYPE III BARRICADE	ED	560.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,091.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	128.000
	0110- 1- 1	CLEARING & GRUBBING (43720215201)	LS	1.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	2.000
	0120- 1-	REGULAR EXCAVATION	CY	305.900
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	628.700
	0160- 4-	TYPE B STABILIZATION	SY	296.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	173.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	2,241.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	13.900
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	199.000
	0570- 1- 1	PERFORMANCE TURF	SY	4,323.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,758.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.361
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.361
Section 0003 Signing				
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43720215201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.379
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.190