

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT200729 Call Order: 017 Proposal: T4553 District:04
 Counties: PALM BEACH
 Road Name: NE 5TH AVE
 Limits: FROM BOCA RATON RD NORTHERLY TO SR 5 (US 1)
 Project(s): 43840215201(*) Federal Aid No: D419081B
 Total Roadway Length: 1.119 Miles Contract Days: 260
 Total Bridge Length: 0.000 Miles Letting Date: 07/29/20
 Total Proposal Length: 1.119 Miles Contract Execution Days: 10
 Special Start Date: 04/01/21
 Aquis/Flexible Start Time: N/A

Proposal Budget Estimate: \$540,483.00

Please read the full advertisement

Description: SPECIAL START DATE

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at: <https://www.fdot.gov/equalopportunity/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at: <http://www.cmdp-bgp.com/bdi-projects.html>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: fdot.bdi@dot.state.fl.us.

All Sublet work must be contracted to a small business or businesses as defined by the Department. The subcontractor must also submit a notarized Small Business Affidavit Form provided by the Department prior to the start of work.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the project's major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the Expedite application.

BDI Reference Sheet may be found at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

The improvements under this contract consist of but are not limited to, concrete (sidewalk and driveways, curb and gutter), pavers, monitor existing structures (inspection and settlement), minor signing (single post; install, relocate, remove) and minor pavement markings (thermoplastic), selective clearing and grubbing, landscaping (relocations, irrigation system repairs), and utility adjustments (manholes) along NE 5th Ave.

Call Order: 017 Proposal: T4553

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43840215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43840215201)	LS	1.000

Call Order: 017 Proposal: T4553

ALT	Item	Description	Unit	Quantity
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	104.400
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (43840215201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	6,760.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	14,300.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	20,223.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	14.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,096.000
	0102-115-	TYPE III BARRICADE	ED	28.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.040
	0104- 10- 3	SEDIMENT BARRIER	LF	4,574.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43840215201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43840215201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.280
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,586.000
	0110- 21-	TREE PROTECTION BARRIER	LF	2,631.000
	0120- 1-	REGULAR EXCAVATION	CY	160.400
	0120- 6-	EMBANKMENT	CY	89.800
	0285-713-	OPTIONAL BASE, BASE GROUP 13	SY	210.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	16.800
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	2.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	73.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	2,796.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	836.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	27.000
	0527- 2-	DETECTABLE WARNINGS	SF	521.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,622.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43840215201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	3.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	12.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	12.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	29.000
Section 0003 Landscape / Peripheral				
	0581- 1- 4	RELOCATE TREES AND PALMS, TREES, <5" DIAMETER AT BREAST HEIGHT	EA	2.000
	0581- 1- 7	RELOCATE TREES AND PALMS, PALMS, <14' OF CLEAR TRUNK, SABAL PALM ONLY	EA	1.000
	0590- 70- 1	IRRIGATION SYSTEM REPAIRS (43840215201)	LS	1.000