

**Florida Department of Transportation  
 Bid Solicitation Notice and Approximate Quantities**

Letting: CT200729 Call Order: 020 Proposal: T5714 District:05  
 Counties: LAKE  
 Road Name: SR 19  
 Limits: FROM EAST FLORAL AVE TO NORTH EUSTIS ST  
 Project(s): 44137015201(\*) Federal Aid No: D520022B  
 Total Roadway Length: 0.236 Miles Contract Days: 120  
 Total Bridge Length: 0.000 Miles Letting Date: 07/29/20  
 Total Proposal Length: 0.236 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 30 Calendar Days  
 Proposal Budget Estimate: \$538,537.00

Please read the full advertisement

Description:  
 BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at: <https://www.fdot.gov/equalopportunity/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at:  
<http://www.cmdp-bgp.com/bdi-projects.html>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: [fdot.bdi@dot.state.fl.us](mailto:fdot.bdi@dot.state.fl.us).

All Sublet work must be contracted to a small business or businesses as defined by the Department. The subcontractor must also submit a notarized Small Business Affidavit Form provided by the Department prior to the start of work.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the project's major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the Expedite application.

BDI Reference Sheet may be found at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

The improvements under this contract consist of milling & resurfacing, drainage improvements, curb & gutters, highway signing, sidewalks and other incidental construction on SR 19.

**Call Order: 020 Proposal: T5714**

ALT	Item	Description	Unit	Quantity
	<b>Section 0001 Roadway</b>			
	0101- 1-	MOBILIZATION (44137015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44137015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,640.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,160.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	120.000

**Call Order: 020 Proposal: T5714**

ALT	Item	Description	Unit	Quantity
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	376.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	120.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	3.000
	0107- 1-	LITTER REMOVAL	AC	4.570
	0107- 2-	MOWING	AC	2.400
	0110- 1- 1	CLEARING & GRUBBING (44137015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	699.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	911.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44137015201)	LS	1.000
	0285-708-	OPTIONAL BASE, BASE GROUP 08	SY	301.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	5,823.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	57.900
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	504.700
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	1.000
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	4.000
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0425- 15- 41	INLET TOP, REPAIR, CURB INLET	EA	1.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	71.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	4.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,085.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	115.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	589.000
	0522- 3-	BUS BOARDING PAD- CONCRETE	SY	8.000
	0527- 2-	DETECTABLE WARNINGS	SF	164.000
	0536- 73-	GUARDRAIL REMOVAL	LF	164.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,837.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.930
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	547.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	101.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.262
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.252
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44137015201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	5.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	7.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	10.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	11.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	24.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44137015201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	547.000

**Call Order: 020 Proposal: T5714**

ALT	Item	Description	Unit	Quantity
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	64.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	101.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	167.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.239
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.025
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.262
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.252