

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT200325 Call Order: 003 Proposal: T1773 District:01
 Counties: POLK
 Road Name: SR 600 (US 92)
 Limits: AT SR 559 (MAIN ST)
 Project(s): 44067215201(*) Federal Aid No: D120004B
 Total Roadway Length: 0.272 Miles Contract Days: 75
 Total Bridge Length: 0.000 Miles Letting Date: 03/25/20
 Total Proposal Length: 0.272 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Days

Proposal Budget Estimate: \$204,912.00

Please read the full advertisement

Description:

The improvements under this contract consist of closing the median openings at Lime Street and Lemon Street, and extending the left turn lanes at the intersection of SR 600 (US 92) at SR 559 (Main Street) in Polk County.

Call Order: 003 Proposal: T1773

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44067215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44067215201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,575.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,710.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	150.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	178.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	75.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	75.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	12.000
	0107- 1-	LITTER REMOVAL	AC	2.340
	0107- 2-	MOWING	AC	0.750
	0110- 1- 1	CLEARING & GRUBBING (44067215201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	195.000
	0120- 1-	REGULAR EXCAVATION	CY	50.700
	0160- 4-	TYPE B STABILIZATION	SY	909.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	663.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	448.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	127.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76 -22	TN	91.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	411.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	65.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44067215201)	LS	1.000
Section 0002 Signage				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	4.000

Call Order: 003 Proposal: T1773

ALT	Item	Description	Unit	Quantity
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	3.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	10.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	2.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	6.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44067215201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.031
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	7.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	61.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	9.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.122
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.260
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	113.000
Section 0003 Signalization				
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	2.000