

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT200325	Call Order: 005	Proposal: T2764	District:02
Counties:	CLAY			
Road Name:	SR 15 (US 17)			
Limits:	AT GOVERNORS CREEK BR			
Project(s):	44140615201(*)	Federal Aid No: D219090B		
Total Roadway Length:	0.061 Miles	Contract Days:	180	
Total Bridge Length:	0.062 Miles	Letting Date:	03/25/20	
Total Proposal Length:	0.123 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days (Acq. time)	
Proposal Budget Estimate:	\$1,110,653.00			

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, shoulder treatment, drainage improvements, curb and gutters, highway signing, guardrail, bridges, sidewalks/bicycle path and other incidental construction on SR 15/US 17 at Governors Creek Bridge in Clay County from MP 1.213 to MP 1.336.

Call Order: 005 Proposal: T2764

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44140615201-710006)	LS	1.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	13.200
	0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	97.400
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	17,650.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	2,254.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I Poured joint with backer rod	LF	271.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, Poured joint with backer rod	LF	642.000
	0515- 4- 2	BULLET RAIL, DOUBLE RAIL	LF	740.000
	0521- 5- 8	CONCRETE TRAFFIC RAILING- BRIDGE,RETROFIT-VERTICAL FACE	LF	740.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44140615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44140615201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	6,810.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	600.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	600.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,600.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	80.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	180.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	1,248.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	388.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	3.000
	0104- 10- 3	SEDIMENT BARRIER	LF	712.000

Call Order: 005 Proposal: T2764

ALT	Item	Description	Unit	Quantity
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0107- 1-	LITTER REMOVAL	AC	3.040
	0107- 2-	MOWING	AC	2.200
	0110- 1- 1	CLEARING & GRUBBING (44140615201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	314.000
	0120- 1-	REGULAR EXCAVATION	CY	32.000
	0120- 6-	EMBANKMENT	CY	46.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	4,591.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	350.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	7.700
	0425- 1-341	INLETS, CURB, TYPE P-4, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	1.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	1.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	18.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	20.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0515- 2-211	PEDESTRIAN / BICYCLE RAILING, STEEL, 42" TYPE 1	LF	426.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	248.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	97.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	392.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	300.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	150.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	4.000
	0536- 8- 12	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-2	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	260.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	288.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	2.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.030
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.607
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44140615201)	LS	1.000
Section 0003 Signing				
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44140615201)	LS	1.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	251.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.246

Call Order: 005 Proposal: T2764

ALT	Item	Description	Unit	Quantity
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.246
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.492