

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT200325 Call Order: 010 Proposal: T3751 District:03
 Counties: WALTON
 Road Name: SR 81
 Limits: AT THE INTERSECTIONS WITH CR 183 AND CR 181
 Project(s): 43775325201(*) Federal Aid No: D319169B
 Total Roadway Length: 2.110 Miles Contract Days: 335
 Total Bridge Length: 0.000 Miles Letting Date: 03/25/20
 Total Proposal Length: 2.110 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Days Standard

Proposal Budget Estimate: \$2,569,909.00

Please read the full advertisement

Description:

The improvements under this contract consist of intersection safety improvements including reconstruction of SR 81 at the intersections with CR 183 and CR 181 in Walton County. Construction items include grading, paving, drainage, earthwork, signing and pavement markings and signalization.

Call Order: 010 Proposal: T3751

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43775325201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43775325201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43775325201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (43775325201)	LS	1.000
	0102- 2- 3	SPECIAL DETOUR 3 (43775325201)	LS	1.000
	0102- 2- 4	SPECIAL DETOUR 4 (43775325201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	71.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	120.000
	0102- 60-	WORK ZONE SIGN	ED	19,510.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,553.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	1,375.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	41,560.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,200.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	1,610.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,785.000
	0104- 10- 3	SEDIMENT BARRIER	LF	5,704.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	15.300
	0107- 2-	MOWING	AC	13.700
	0110- 1- 1	CLEARING & GRUBBING (43775325201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	535.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	5.000
	0120- 1-	REGULAR EXCAVATION	CY	10,600.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	6,773.000

Call Order: 010 Proposal: T3751

ALT	Item	Description	Unit	Quantity
	0120- 4-	SUBSOIL EXCAVATION	CY	5,638.000
	0160- 4-	TYPE B STABILIZATION	SY	3,111.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,529.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	5,175.000
	0285-708-	OPTIONAL BASE, BASE GROUP 08	SY	5,988.000
	0327- 70- 12	MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH	SY	6,607.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	1,090.700
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	910.100
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0425- 3- 41	JUNCTION BOX, DRAINAGE, P-7, <10'	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	336.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	96.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	96.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	17.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	482.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	12,876.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	2.166
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	179.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.418
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43775325201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	18.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	18.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	3.000
	0701- 18-101	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6"	GM	1.252
	0701- 18-201	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.876
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	6.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43775325201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	69.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.478
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.164
Section 0003 Signalization				
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0634- 4-152	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL	PI	1.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	1.000

Call Order: 010 Proposal: T3751

ALT	Item	Description	Unit	Quantity
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	48.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 16	PRESTRESSED CONCRETE POLE, F&I, TYPE P-VI	EA	2.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	2.000
	0650- 1- 11	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 1 SECTION, 1 WAY	AS	2.000
	0650- 1- 12	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 1 SECTION, 2-4 WAY	AS	2.000
	0670- 4- 1	INTERSECTION CONTROL BEACON CONTROLLER ASSEMBLY, FURNISH & INSTALL	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000