

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT200325 Call Order: 019 Proposal: T6475 District:06
 Counties: MIAMI-DADE
 Road Name: SR 976 (SW 40 ST) (BIRD RD)
 Limits: FROM E OF SW 117 AVE TO E OF SW 102 AVE AND FROM SW 114 AVE TO SW 102 AVE
 Project(s): 43635525201(*) Federal Aid No: D619046B
 Project(s): 43635525601 Federal Aid No: N/A
 Project(s): 43635535201 Federal Aid No: D619053B
 Project(s): 43792315201 Federal Aid No: D619047B
 Total Roadway Length: 3.730 Miles Contract Days: 350
 Total Bridge Length: 0.000 Miles Letting Date: 03/25/20
 Total Proposal Length: 3.730 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 90 Calendar Days
 Proposal Budget Estimate: \$4,281,695.00

Please read the full advertisement: FLEXIBLE START DATE

Description: Incentive / Disincentive

The improvements under this contract consist of resurfacing, drainage improvements, and intersection improvements along SR 976 (SW 40th St.) (Bird Rd.).

Call Order: 019 Proposal: T6475

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43635525201)	LS	1.000
	0101- 1-	MOBILIZATION (43635535201)	LS	1.000
	0101- 1-	MOBILIZATION (43792315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43635525201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43635535201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43792315201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	728.000
	0102- 60-	WORK ZONE SIGN	ED	12,570.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	2,405.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	27,590.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,450.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	366.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,470.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	2,263.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,124.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	2,000.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	2,000.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	65.000
	0107- 1-	LITTER REMOVAL	AC	49.000
	0107- 2-	MOWING	AC	38.310

Call Order: 019 Proposal: T6475

ALT	Item	Description	Unit	Quantity
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43635525201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43635525201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43635525201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43635535201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43792315201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.710
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,200.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	169.200
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43635525201)	LS	1.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43792315201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	3,171.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	539.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	2,460.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	8,998.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	65,792.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	4,077.100
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	4,128.400
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	7.000
	0425- 1-359	INLETS, CURB, TYPE P-5, MODIFY	EA	3.000
	0425- 1-369	INLETS, CURB, TYPE P-6, MODIFY	EA	7.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	7.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	5.000
	0425- 4-	INLETS, ADJUST	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	4.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	14.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	84.000
	0443- 70- 4	FRENCH DRAIN, 24"	LF	1,625.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	4,837.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	309.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	956.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,484.000
	0527- 2-	DETECTABLE WARNINGS	SF	836.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,979.000
	0639- 8- 27	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), PROJECT 437923-1-52-01 (DO NOT BID) (43792315201)	LS	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	5.717
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.244
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,991.000

Call Order: 019 Proposal: T6475

ALT	Item	Description	Unit	Quantity
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	230.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	3,980.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	5.893
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.037
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	72.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.158
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	273.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.039
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43635525201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43635535201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43792315201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	50.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	10.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	8.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	8.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	54.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	8.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	401.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43635525201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43792315201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	578.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	230.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	990.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.037
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	72.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	273.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.120
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	3,413.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,990.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.218
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.244
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	5.133

Call Order: 019 Proposal: T6475

ALT	Item	Description	Unit	Quantity
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.158
Section 0003 Lighting				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	26.000
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	5,091.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	5.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	5.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	115.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	6.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	600.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	320.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	22.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	5.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	3.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	3.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	5.000
	0649- 26- 7	STEEL MAST ARM ASSEMBLY, REMOVE, REMOVE ARM AND ATTACHMENTS; POLE REMAINS	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	20.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	3.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	20.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	5.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	13.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	5.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	21.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	32.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	9.000
	0670- 5-140	TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL MODEL 207	AS	5.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	5.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	14.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	15.000

Call Order: 019 Proposal: T6475

ALT	Item	Description	Unit	Quantity
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	6.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	2.000
Section 0005 Landscape / Peripheral				
	0580- 2- 1	LANDSCAPE- RELOCATE TREE, PALMS <14' OF CLEAR TRUNK	EA	1.000
	0580- 2- 2	LANDSCAPE- RELOCATE TREE, PALMS >14' OF CLEAR TRUNK	EA	6.000
Section 0006 Utilities				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43635525601)	LS	1.000
	1060- 15-	UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	EA	2.000
	1080- 24-500	UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	EA	35.000