

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT200325	Call Order: 021	Proposal: T7437	District:07
Counties:	PINELLAS			
Road Name:	BOOKER CREEK BR			
Limits:	OVER BOOKER CREEK			
Project(s):	43605615201(*)	Federal Aid No: D719047B		
Total Roadway Length:	0.050 Miles	Contract Days:	268	
Total Bridge Length:	0.116 Miles	Letting Date:	03/25/20	
Total Proposal Length:	0.166 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Calendar Days	

Proposal Budget Estimate: \$1,409,476.00

Please read the full advertisement

**Description:**

The improvements under this contract consist of rehabilitation, repair, and replacement of bridge culvert Bridge 157235, non-vibratory press-in permanent sheet pile walls, excavation, embankment, removal and installation of roadway brick pavers, removal and installation of sidewalk concrete pavers, removal and installation of granite curb, sidewalk, driveway, curb, selective clearing and grubbing, and asphalt pavement. Bridge culvert Bridge 157235 is part of the Booker Creek basin handling flows under 10th Ave. South, 5th St. South, and 11th Ave. South, all City of St Petersburg facilities, from Booker Creeks main channel to the outfall. This project is in a neighborhood surrounded by historically significant structures and locations. Archeological monitoring shall be provided by the Department when work is anticipated to disturb soil, brick roadway pavers, or concrete sidewalk pavers.

**Call Order: 021 Proposal: T7437**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43605615201)	LS	1.000
	0400- 3- 20	CONC CLASS III, SEAL	CY	79.000
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	29.700
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	1,541.400
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	3.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	113.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	7,204.000
	0455-133-203	STEEL SHEET PILING, NON-VIBRATORY PRESS-IN METHOD REQUIRED, PROJECT 436056-1-52-01	SF	3,965.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (43605615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43605615201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	4.000
	0102- 60-	WORK ZONE SIGN	ED	8,640.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,060.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	704.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	84.000
	0104- 10- 3	SEDIMENT BARRIER	LF	55.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	99.000
	0107- 1-	LITTER REMOVAL	AC	3.330

**Call Order: 021 Proposal: T7437**

ALT	Item	Description	Unit	Quantity
	0107- 2-	MOWING	AC	1.400
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43605615201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43605615201)	LS	1.000
	0108- 3-	MONITOR EXISTING STRUCTURES- GROUNDWATER MONITORING (43605615201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.270
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	58.000
	0120- 1-	REGULAR EXCAVATION	CY	27.700
	0120- 6-	EMBANKMENT	CY	329.400
	0125- 1-	EXCAVATION FOR STRUCTURES	CY	164.200
	0160- 4-	TYPE B STABILIZATION	SY	662.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	181.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	423.000
	0337- 7- 85	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC D, FC-12.5, PG 76-22	TN	15.000
	0520- 2- 1	CONCRETE CURB, TYPE A	LF	27.000
	0520- 7- 2	GRANITE CURB, RESET	LF	480.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	51.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	48.000
	0526- 1- 1	PAVERS, ARCHITECTURAL, ROADWAY	SY	423.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK (match existing pattern)	SY	33.000
	0527- 2-	DETECTABLE WARNINGS	SF	8.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	443.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	1.000
<b>Section 0003</b>	<b>Signing</b>			
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000