

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT200325 Call Order: 022 Proposal: T7441 District:07
 Counties: PINELLAS
 Road Name: SR 693 (66TH ST)
 Limits: FROM 30TH AVE N TO 58TH AVE N
 Project(s): 43764315201(*) Federal Aid No: D719045B
 Total Roadway Length: 1.346 Miles Contract Days: 122
 Total Bridge Length: 0.388 Miles Letting Date: 03/25/20
 Total Proposal Length: 1.734 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 120 Calendar Days

Proposal Budget Estimate: \$1,709,000.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, signing and marking, signal and sidewalk improvements. As well as, reconstructing the median of SR 693 (66th St. N).

Call Order: 022 Proposal: T7441

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|-------------|--|------|------------|
| Section 0001 Roadway | | | | |
| | 0101- 1- | MOBILIZATION (43764315201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (43764315201) | LS | 1.000 |
| | 0102- 14- | TRAFFIC CONTROL OFFICER | HR | 20.000 |
| | 0102- 60- | WORK ZONE SIGN | ED | 5,386.000 |
| | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED | 20,596.000 |
| | 0102- 74- 2 | CHANNELIZING DEVICE, TYPE III, 6' | ED | 268.000 |
| | 0102- 76- | ARROW BOARD / ADVANCE WARNING ARROW PANEL | ED | 540.000 |
| | 0102- 99- | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY | ED | 403.000 |
| | 0104- 18- | INLET PROTECTION SYSTEM | EA | 51.000 |
| | 0107- 1- | LITTER REMOVAL | AC | 19.260 |
| | 0107- 2- | MOWING | AC | 7.440 |
| | 0110- 1- 1 | CLEARING & GRUBBING (43764315201) | LS | 1.000 |
| | 0110- 4- 10 | REMOVAL OF EXISTING CONCRETE | SY | 2,664.000 |
| | 0120- 6- | EMBANKMENT | CY | 771.100 |
| | 0285-715- | OPTIONAL BASE, BASE GROUP 15 | SY | 8,485.000 |
| | 0327- 70- 6 | MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH | SY | 938.000 |
| | 0334- 1- 13 | SUPERPAVE ASPHALTIC CONC, TRAFFIC C | TN | 1,166.600 |
| | 0337- 7- 83 | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22 | TN | 780.000 |
| | 0520- 1- 10 | CONCRETE CURB & GUTTER, TYPE F | LF | 506.000 |
| | 0520- 2- 1 | CONCRETE CURB, TYPE A | LF | 3,285.000 |
| | 0520- 5- 41 | TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE | LF | 915.000 |
| | 0520- 70- | CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH | SY | 1,061.000 |
| | 0522- 1- | CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK | SY | 26.000 |
| | 0522- 2- | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK | SY | 40.000 |
| | 0527- 2- | DETECTABLE WARNINGS | SF | 91.000 |

Call Order: 022 Proposal: T7441

| ALT | Item | Description | Unit | Quantity |
|-----------------------------------|--------------|--|------|-----------|
| | 0570- 1- 2 | PERFORMANCE TURF, SOD | SY | 1,750.000 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (43764315201) | LS | 1.000 |
| Section 0002 Signing | | | | |
| | 0700- 1- 11 | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF | AS | 25.000 |
| | 0700- 1- 12 | SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF | AS | 15.000 |
| | 0700- 1- 13 | SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF | AS | 3.000 |
| | 0700- 1- 50 | SINGLE POST SIGN, RELOCATE | AS | 15.000 |
| | 0700- 1- 60 | SINGLE POST SIGN, REMOVE | AS | 7.000 |
| | 0700- 2- 50 | MULTI- POST SIGN, GROUND MOUNT, RELOCATE | AS | 1.000 |
| | 0700- 3-101 | SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF | EA | 1.000 |
| | 0700- 3-201 | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF | EA | 4.000 |
| | 0700- 3-601 | SIGN PANEL, REMOVE, UP TO 12 SF | EA | 17.000 |
| | 0700- 5- 22 | INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF | EA | 2.000 |
| | 0705- 11- 3 | DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN | EA | 40.000 |
| | 0710- 11-190 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE | SF | 32.000 |
| | 0710- 11-290 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE | SF | 32.000 |
| | 0710- 90- | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43764315201) | LS | 1.000 |
| | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT | LF | 1,762.000 |
| | 0711- 11-124 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS | LF | 280.000 |
| | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK | LF | 88.000 |
| | 0711- 11-141 | THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" | GM | 0.473 |
| | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL | EA | 1.000 |
| | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW | EA | 50.000 |
| | 0711- 11-241 | THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6" | GM | 0.202 |
| | 0711- 14-125 | THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK | LF | 1,219.000 |
| | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" | GM | 0.246 |
| | 0711- 16-102 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8" | GM | 0.976 |
| | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" | GM | 2.607 |
| | 0711- 17- 1 | THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN | SF | 5,289.000 |
| Section 0003 Signalization | | | | |
| | 0630- 2- 11 | CONDUIT, FURNISH & INSTALL, OPEN TRENCH | LF | 102.000 |
| | 0630- 2- 12 | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE | LF | 204.000 |
| | 0632- 7- 1 | SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL | PI | 1.000 |
| | 0635- 2- 11 | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE | EA | 10.000 |
| | 0635- 2- 12 | PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE | EA | 2.000 |
| | 0639- 1-122 | ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR | AS | 1.000 |

Call Order: 022 Proposal: T7441

| ALT | Item | Description | Unit | Quantity |
|-----|-------------|---|------|----------|
| | 0639- 2- 1 | ELECTRICAL SERVICE WIRE, FURNISH & INSTALL | LF | 5.000 |
| | 0641- 2- 12 | PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE | EA | 1.000 |
| | 0646- 1- 12 | ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST | EA | 2.000 |
| | 0649- 21- 6 | STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50' | EA | 2.000 |
| | 0653- 1- 11 | PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY | AS | 2.000 |
| | 0654- 3- 10 | PEDESTRIAN HYBRID BEACON ASSEMBLY, FURNISH & INSTALL COMPLETE ASSEMBLY | AS | 6.000 |
| | 0665- 1- 11 | PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD | EA | 2.000 |
| | 0670- 5-110 | TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA | AS | 1.000 |
| | 0685- 1- 12 | UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION | EA | 1.000 |