

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	CT200520	Call Order: 003	Proposal: T1764	District:01
Counties:	LEE			
Road Name:	SR 865			
Limits:	AT VARIOUS LOCATIONS AS LISTED IN THE PLANS			
Project(s):	44013015201(*)	Federal Aid No:	D120008B	
Total Roadway Length:	3.741 Miles	Contract Days:	100	
Total Bridge Length:	0.000 Miles	Letting Date:	05/20/20	
Total Proposal Length:	3.741 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Days (Aqui Time)	
Proposal Budget Estimate:	\$316,917.00			

Please read the full advertisement

Description:

The improvements under this contract consist of retrofit lighting systems at five intersections along SR 865/San Carlos Blvd. These are at Prescott Street, Pineridge Road, White Water Court, Kelly Road, and at Gladiolus Drive, in Lee County. The project will include converting existing fixtures from HPS to LED and adding new light poles at locations indicated in the plans.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 003 Proposal: T1764**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44013015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44013015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,300.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,200.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	200.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	185.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	100.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	500.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	500.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	17.000
	0107- 1-	LITTER REMOVAL	AC	1.490
	0107- 2-	MOWING	AC	1.000
	0110- 1- 1	CLEARING & GRUBBING (44013015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	84.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	67.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44013015201)	LS	1.000
<b>Section 0002 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	513.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,646.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	23.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	5.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	250.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	7,263.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	11.000
	0715- 4- 23	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT	EA	5.000
	0715- 4- 31	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 30' MOUNTING HEIGHT	EA	1.000
	0715- 4- 41	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, SPECIAL FOUNDATION, 30' MOUNTING HEIGHT	EA	1.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	5.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	18.000