

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT200520 Call Order: 004 Proposal: T2757 District:02

Counties: DUVAL

Road Name: SR 113

Limits: FROM SR 115 TO I-295

Project(s): 43761115201(*)

Federal Aid No: D219055B

Total Roadway Length:	2.448 Miles	Contract Days:	400
Total Bridge Length:	0.233 Miles	Letting Date:	05/20/20
Total Proposal Length:	2.681 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	90 Days

Proposal Budget Estimate: \$10,270,125.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, curb and gutters, traffic signals, lighting, highway signing, guardrail, sidewalks/bicycle path, and other incidental construction on SR 113 in Duval County from SR 115 to I-295.

Call Order: 004 Proposal: T2757

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43761115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43761115201)	LS	1.000
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (43761115201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	336.000
	0102- 60-	WORK ZONE SIGN	ED	25,144.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	1,350.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	3,517.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	272,568.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	147.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	2,580.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	875.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	3,138.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	10.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	901.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	2,800.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	2,800.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	1,200.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	1,200.000
	0104- 10- 3	SEDIMENT BARRIER	LF	12,106.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	154.000
	0107- 1-	LITTER REMOVAL	AC	1,270.750
	0107- 2-	MOWING	AC	817.490

Call Order: 004 Proposal: T2757

ALT	Item	Description	Unit	Quantity
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43761115201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43761115201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,623.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	4,413.700
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43761115201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	421.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	421.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	1,066.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	59,482.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	96,108.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	107,504.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	7,680.800
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	7,597.900
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	3,842.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	10,856.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	950.100
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	23.400
	0425- 1-352	INLETS, CURB, TYPE P-5, >10'	EA	1.000
	0425- 1-455	INLETS, CURB, TYPE J-5, PARTIAL	EA	1.000
	0425- 1-515	INLETS, DT BOT, TYPE B, PARTIAL	EA	19.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	2.000
	0425- 1-702	INLETS, GUTTER, TYPE S, >10'	EA	2.000
	0425- 1-891	INLETS, BARRIER WALL, <=10'	EA	3.000
	0425- 5-	MANHOLE, ADJUST	EA	10.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	6.000
	0425- 6-	VALVE BOXES, ADJUST	EA	8.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	496.000
	0430-613-123	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:4 SLOPE,15"PIPE	EA	1.000
	0430-613-125	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:4 SLOPE,18"PIPE	EA	1.000
	0430-613-129	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:4 SLOPE, 24"PIPE	EA	1.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	2.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	595.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,523.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	40.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	1,905.000
	0521- 1- 13	MEDIAN CONCRETE BARRIER, TALL GRADE-SEPARATED	LF	35.000
	0521- 72- 56	SHOULDER CONCRETE BARRIER, 56" PIER PROTECTION BARRIER/CRASH WALL	LF	690.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,876.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	664.000
	0527- 2-	DETECTABLE WARNINGS	SF	815.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	1,424.600

Call Order: 004 Proposal: T2757

ALT	Item	Description	Unit	Quantity
	0530- 74-	BEDDING STONE	TN	1,023.600
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	10,464.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	2,010.000
	0536- 5- 1	RUB RAIL FOR GUARDRAIL, SINGLE SIDED RUB RAIL	LF	1,313.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	49.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	10.000
	0536- 73-	GUARDRAIL REMOVAL	LF	2,737.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	31.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	25.000
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	12.000
	0536- 85- 29	GUARDRAIL END TREATMENT- DOUBLE FACE TRAILING ANCHORAGE	EA	1.000
	0538- 1-	GUARDRAIL RESET	LF	950.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	2.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	1.875
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	263.000
	0570- 1- 1	PERFORMANCE TURF	SY	8,402.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	10,899.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	6.336
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	1.562
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	260.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	350.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	94.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	6.697
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.317
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.004
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	7.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	5.442
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.032
	0919-528- 2	DIRECTIONAL INDICATORS, PROJECT 437611-1-52-01	SF	59.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43761115201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	57.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	25.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	10.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	6.000

Call Order: 004 Proposal: T2757

ALT	Item	Description	Unit	Quantity
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	42.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	2.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	2.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	15.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	4.000
	0700- 3-208	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	3.000
	0700- 3-625	SIGN PANEL, REMOVE, 51-100 SF WITH LIGHTING	EA	2.000
	0700- 3-626	SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING	EA	13.000
	0700- 3-627	SIGN PANEL, REMOVE PANEL, 201-300 SF WITH LIGHTING	EA	3.000
	0700- 3-628	SIGN PANEL, REMOVE PANEL, 301-400 SF WITH LIGHTING	EA	2.000
	0700- 4-127	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 151-200 FT	EA	1.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	18.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	6.000
	0701- 18-101	PROFIED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	2.293
	0701- 18-201	PROFIED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	4.006
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	132.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43761115201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.083
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	2.774
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	3,195.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,000.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,098.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.980
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	19.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	160.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	15.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	54.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.067
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,836.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	27.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	27.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	2.813

Call Order: 004 Proposal: T2757

ALT	Item	Description	Unit	Quantity
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	5.569
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.318
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	1.185
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	10.824
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	4.659
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.069
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	6.259
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.815
	0713-103-103	PERMANENT TAPE, WHITE, SOLID LANE DROP MARKING, 12" FOR CONCRETE BRIDGES	GM	0.051
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	1.427
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.816
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	1.427
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,777.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	10.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	8,223.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	99.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	2,646.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	3.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	4.000
	0715- 11-212	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY HIGH MAST	EA	174.000
	0715- 11-225	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE, ROADWAY, WALL MOUNT	EA	20.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	4.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	3.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	132.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,689.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	6.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	960.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	90.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	3.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	3.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	8.000

Call Order: 004 Proposal: T2757

ALT	Item	Description	Unit	Quantity
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	6.000
	0634- 4-154	SPAN WIRE ASSEMBLY, F&I, TWO POINT, OTHER TYPE	PI	1.000
	0634- 4-600	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	22.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	1.000
	0639- 1-123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	370.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	3.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	25.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	12.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000
	0649- 21- 11	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 60'-30'	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	55.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	7.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	2.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	57.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	34.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	14.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	34.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	63.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	40.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	20.000
	0670- 5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	6.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	4.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	4.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	5.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	8.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	12.000