

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT200520	Call Order: 007	Proposal: T3737	District:03
Counties:	FRANKLIN			
Road Name:	SR 30 (US 98)			
Limits:	FROM CR 30A (GULF AVE) TO LAKE MORALITY RD			
Project(s):	44174415201(*)	Federal Aid No: D319132B		
Total Roadway Length:	1.984 Miles	Contract Days:	60	
Total Bridge Length:	0.000 Miles	Letting Date:	05/20/20	
Total Proposal Length:	1.984 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Day Standard	

Proposal Budget Estimate: \$244,007.00

Please read the full advertisement

Description:

The improvements under this contract consist of signing and pavement marking improvements on SR 30 (US 98) from Gulf Avenue to Lake Morality Road in Franklin County.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 007 Proposal: T3737

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44174415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44174415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,860.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	7,552.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	148.000
	0107- 1-	LITTER REMOVAL	AC	22.050
	0107- 2-	MOWING	AC	21.490
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44174415201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	50.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	16.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	0700- 12- 21	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, ONE BEACON	AS	6.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	3.812
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	2.701
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0706- 1- 1	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS	EA	1,053.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.867
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.036
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.753
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.052
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.036
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	2.000
	0711- 12-201	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6"	GM	0.351
	0711- 12-231	THERMOPLASTIC, REFURBISHMENT, YELLOW, SKIP, 6"	GM	0.546
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.103
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.052
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.052
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	17,573.000
Section 0003 Signalization				
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	2.000