

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT200520	Call Order: 008	Proposal: T3738	District:03
Counties:	ESCAMBIA			
Road Name:	SR 10 (US 90A)			
Limits:	FROM N PALAFOX ST TO CHEMSTRAND RD			
Project(s):	44173815201(*)	Federal Aid No:	D319130B	
Project(s):	44173815202	Federal Aid No:	N/A	
Total Roadway Length:	0.693 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	05/20/20	
Total Proposal Length:	0.693 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days Acquis.	
Proposal Budget Estimate:	\$1,289,820.00			

Please read the full advertisement

**Description:**

The improvements for SR 10 (US 90A) East Nine Mile Road from N. Palafox Street to Chemstrand Road in Escambia County consist of the following items, which were recommended in the Updated Safety Analysis, dated July 21, 2017: Upgrading traffic signals at the intersections of Palafox Street, Holsberry Road and Chemstrand Road; Modifying the medians along SR10 (US 90A) East Nine Mile Road from N. Palafox Street to Chemstrand Road; Removing the acceleration tapers located along the corridor of SR 10 (US 90A) East Nine Mile Road from N. Palafox Street to Chemstrand Road; Adding left turn lanes at the unsignalized intersections that do not have left turn lanes. Improvements also include FPID 441738-1-52-02 Utility Work by Highway Contractor (UWHC) to adjust 1 manhole for Emerald Coast Utility Authority (ECUA).

**Call Order: 008 Proposal: T3738**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44173815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44173815201)	LS	1.000
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (44173815201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	48.000
	0102- 60-	WORK ZONE SIGN	ED	6,610.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	13,560.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	720.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	388.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	540.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	540.000
	0104- 10- 3	SEDIMENT BARRIER	LF	4,962.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000
	0107- 1-	LITTER REMOVAL	AC	45.940
	0107- 2-	MOWING	AC	30.490
	0110- 1- 1	CLEARING & GRUBBING (44173815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	336.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	9.000
	0120- 1-	REGULAR EXCAVATION	CY	2,005.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,323.100
	0160- 4-	TYPE B STABILIZATION	SY	6,354.000

**Call Order: 008 Proposal: T3738**

ALT	Item	Description	Unit	Quantity
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,304.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	3,405.000
	0327- 70- 12	MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH	SY	14,166.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	571.100
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-9.5, PG 76-22	TN	1,289.700
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	2.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	42.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	51.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	5.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	107.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	56.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	638.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	233.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	417.000
	0520- 5- 12	TRAFFIC SEPARATOR CONCRETE-TYPE I, 6' WIDE	LF	207.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	203.000
	0527- 2-	DETECTABLE WARNINGS	SF	120.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	7,759.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.877
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.254
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	2,442.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	154.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	324.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.024
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.190
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	57.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.689
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.057
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44173815201)	LS	1.000

**Call Order: 008 Proposal: T3738**

ALT	Item	Description	Unit	Quantity
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	10.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	6.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	7.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	2.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	7.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	143.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44173815201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,907.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	154.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	324.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.009
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	57.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.057
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,806.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	17.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	17.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.877
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.254
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"-APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.024
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.689
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	293.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,085.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	3.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	24.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	23.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	12.000
	0650- 2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	23.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	22.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	3.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	6.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	24.000

**Call Order: 008 Proposal: T3738**

ALT	Item	Description	Unit	Quantity
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	4.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	3.000
<b>Section 0004 Utilities</b>				
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44173815202)	LS	1.000