

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	CT200520	Call Order: 010	Proposal: T4552	District:04
Counties:	BROWARD			
Road Name:	SR 9 (I-95)			
Limits:	AT COPANS RD INTERCHANGE			
Project(s):	43696215201(*)	Federal Aid No:	D419098B	
Project(s):	43696215202	Federal Aid No:	D419098B	
Total Roadway Length:	1.199 Miles	Contract Days:	642	
Total Bridge Length:	0.055 Miles	Letting Date:	05/20/20	
Total Proposal Length:	1.254 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Calendar Days	
Proposal Budget Estimate:	\$27,583,008.00			

Please read the full advertisement

**Description:**

The improvements under this contract consist of, but not limited to, reconstruction, widening, milling and resurfacing (asphalt), bridge widening, sidewalk, drainage improvements including curb and gutter, shoulder gutter and storm water ponds, pipe desilting, construction of noise walls, retaining walls, pier protection barrier walls, express lane delineators, installation of ITS conduits and equipment, signing and pavement markings, vehicle detection, ITS cameras, lighting, landscaping and interchange modification of on and off ramps along SR 9 (I-95).

**Call Order: 010 Proposal: T4552**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (436962-1-52-01 Bridge No: 860120)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (436962-1-52-01 Bridge No: 860220)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	430.500
	0400- 2- 5	CONCRETE CLASS II, BRIDGE SUBSTRUCTURE	CY	200.800
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	108.200
	0400- 2- 25	CONCRETE CLASS II, MASS, BRIDGE SUBSTRUCTURE	CY	120.600
	0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	1,666.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	14,630.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	33.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	93,182.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	87,010.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	20,316.000
	0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	2,019.000
	0455- 34-325	PRESTRESSED CONCRETE PILING, INCLUDES 100% DYNAMIC TESTING, PROJECT 436962-1-52-01, SIZE 18"	LF	5,755.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	5,970.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	342.000
	0506- 2-	BRIDGE DRAINAGE PIPE	LF	142.000
	0506- 3-	BRIDGE DRAINS	EA	3.000
	0521- 5- 12	CONCRETE TRAFFIC RAILING- BRIDGE, 36" MEDIAN SINGLE SLOPE	LF	684.000

**Call Order: 010 Proposal: T4552**

ALT	Item	Description	Unit	Quantity
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	684.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	2,048.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	18.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (43696215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43696215201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43696215201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (43696215201)	LS	1.000
	0102- 2- 3	SPECIAL DETOUR 3 (43696215201)	LS	1.000
	0102- 2- 4	SPECIAL DETOUR 4 (43696215201)	LS	1.000
	0102- 2- 5	SPECIAL DETOUR 5 (43696215201)	LS	1.000
	0102- 2- 6	SPECIAL DETOUR 6 (43696215201)	LS	1.000
	0102- 2- 7	SPECIAL DETOUR 7 (43696215201)	LS	1.000
	0102- 2- 8	SPECIAL DETOUR 8 (43696215201)	LS	1.000
	0102- 2- 9	SPECIAL DETOUR 9 (43696215201)	LS	1.000
	0102- 2- 10	SPECIAL DETOUR 10 (43696215201)	LS	1.000
	0102- 2- 11	SPECIAL DETOUR 11 (43696215201)	LS	1.000
	0102- 2- 12	SPECIAL DETOUR 12 (43696215201)	LS	1.000
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (43696215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	32.000
	0102- 30- 17	TEMPORARY HIGHWAY LIGHTING, PROJECT 436962-1-52-01 (43696215201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	59,082.000
	0102- 62-	BARRIER MOUNTED WORK ZONE SIGN- INDEX 11871/700-013	ED	122.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	19,300.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	425.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	18,700.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	154,532.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	3,388.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	463.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	793.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	12,213.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	31.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,012.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	642.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	642.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	416.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	332.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.549
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.480
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.274
	0104- 10- 3	SEDIMENT BARRIER	LF	10,564.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	822.000

**Call Order: 010 Proposal: T4552**

ALT	Item	Description	Unit	Quantity
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	1,396.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	57.000
	0107- 1-	LITTER REMOVAL	AC	126.100
	0107- 2-	MOWING	AC	74.940
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43696215201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43696215201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43696215201)	LS	1.000
	0110- 2- 3	SELECTIVE CLEARING AND GRUBBING, PLANT PRESERVATION AREA	AC	16.460
	0120- 1-	REGULAR EXCAVATION	CY	19,013.000
	0120- 6-	EMBANKMENT	CY	82,604.000
	0160- 4-	TYPE B STABILIZATION	SY	41,089.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	12,845.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	1,079.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	24,366.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	2,452.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	2,011.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	36,602.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	4,497.000
	0327- 70- 15	MILLING EXIST ASPH PAVT, 2 3/4" AVG DEPTH	SY	1,087.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	94,795.000
	0327- 70- 20	MILLING EXIST ASPH PAVT, 3 3/4" AVG DEPTH	SY	5,423.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	785.900
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	6,396.100
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	1,024.300
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	279.100
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	5,263.900
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	2,596.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	426.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	9.800
	0400- 2- 11	CONCRETE CLASS II, RETAINING WALLS	CY	437.900
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	45,565.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	2.000
	0425- 1-359	INLETS, CURB, TYPE P-5, MODIFY	EA	1.000
	0425- 1-369	INLETS, CURB, TYPE P-6, MODIFY	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	2.000
	0425- 1-545	INLETS, DITCH BOTTOM, TYPE D, PARTIAL	EA	1.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	1.000
	0425- 1-555	INLETS, DT BOT, TYPE E, PARTIAL	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	36.000
	0425- 1-702	INLETS, GUTTER, TYPE S, >10'	EA	9.000
	0425- 1-891	INLETS, BARRIER WALL, <=10'	EA	16.000

**Call Order: 010 Proposal: T4552**

ALT	Item	Description	Unit	Quantity
	0425- 1-892	INLETS, BARRIER WALL, >10'	EA	1.000
	0425- 1-893	INLETS, BARRIER WALL, J BOT, <10'	EA	16.000
	0425- 1-894	INLETS, BARRIER WALL, J BOT, >10'	EA	5.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	6.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	4.000
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0425- 6-	VALVE BOXES, ADJUST	EA	2.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	6,360.000
	0430- 94- 2	DESILTING PIPE, 25 - 36"	LF	766.000
	0430- 94- 3	DESILTING PIPE, 37 - 48"	LF	368.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	1,087.000
	0430-173-124	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 24", GUTTER DRAIN	LF	70.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	127.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	2,969.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	793.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	752.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	18.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	177.000
	0430-611-125	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 18"PIPE	EA	7.000
	0430-611-129	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 24"PIPE	EA	1.000
	0430-611-325	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE	EA	15.000
	0430-611-329	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 24"PIPE	EA	1.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	2.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	3,350.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	64.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	5,122.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	59.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	197.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	5,798.000
	0521- 1- 12	MEDIAN CONCRETE BARRIER, SHORT GRADE-SEPARATED	LF	2,302.000
	0521- 1- 13	MEDIAN CONCRETE BARRIER, TALL GRADE-SEPARATED	LF	1,328.000
	0521- 1- 14	MEDIAN CONCRETE BARRIER, VARIABLE SECTION WIDTH FOR SIGN OR PIER SHIELDING	LF	448.000
	0521- 8- 7	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	LF	1,693.000
	0521- 72- 24	SHOULDER CONCRETE BARRIER WALL, 8' NOISE WALL	LF	250.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	914.000
	0521- 72- 56	SHOULDER CONCRETE BARRIER, 56" PIER PROTECTION BARRIER/CRASH WALL	LF	707.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	339.000
	0523- 1- 3	PATTERNED PAVEMENT, VEHICULAR AREAS- GREEN BIKE LANE	SY	617.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	8,619.000
	0527- 2-	DETECTABLE WARNINGS	SF	20.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	16.800
	0534- 72-101	SOUND/NOISE BARRIER-INC FOUNDATION, PERMANENT	SF	80,020.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	130.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	7,182.000

**Call Order: 010 Proposal: T4552**

ALT	Item	Description	Unit	Quantity
	0536- 8- 12	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-2	EA	2.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	9.000
	0536- 73-	GUARDRAIL REMOVAL	LF	5,472.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	7.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	9.000
	0544- 2- 1	CRASH CUSHION, TL-2, NARROW	EA	2.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	1.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	1.550
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	23,984.000
	0570- 1- 1	PERFORMANCE TURF	SY	62,634.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	36,230.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	29.000
	0705- 11-111	DELINEATOR, FLEXIBLE HIGH PERFORMANCE 24" MANAGED LANES- EXPRESS LANE MARKER, PROJECT 436962-1-52-01	EA	2,035.000
	0705- 11-112	DELINEATOR, FLEXIBLE HIGH PERFORMANCE 36" MANAGED LANES- EXPRESS LANE MARKER, PROJECT 436962-1-52-01	EA	2,554.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	18.476
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	2.768
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	60.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	88.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	4.694
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.253
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	13.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	2.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	7.998
	0999- 16-	PARTNERING, DO NOT BID (43696215201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	22.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43696215201)	LS	1.000
<b>Section 0003 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	31.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	10.000
	0700- 1- 22	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013, 12-20 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	24.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	3.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	2.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	4.000

**Call Order: 010 Proposal: T4552**

ALT	Item	Description	Unit	Quantity
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	5.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	2.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	9.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	1.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	9.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	9.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	1.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	1.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	8.000
	0700- 4-610	OVERHEAD STATIC SIGN STRUCTURE, REMOVE CANTILEVER	EA	7.000
	0700- 4-620	OVERHEAD STATIC SIGN STRUCTURE, REMOVE SPAN	EA	1.000
	0700- 6- 21	HIGHLIGHTED SIGN, F&I GROUND MOUNT- SOLAR POWERED, UP TO 12 SF	AS	2.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	25.000
	0705- 11-111	DELINEATOR, FLEXIBLE HIGH PERFORMANCE 24" MANAGED LANES- EXPRESS LANE MARKER, PROJECT 436962-1-52-01	EA	697.000
	0705- 11-112	DELINEATOR, FLEXIBLE HIGH PERFORMANCE 36" MANAGED LANES- EXPRESS LANE MARKER, PROJECT 436962-1-52-01	EA	1,877.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	102.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43696215201)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	1.309
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	80.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	196.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	340.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.999
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	15.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	22.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	80.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	10.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	10.000
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	439.000
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT RAILROAD DYNAMIC ENVELOPE	LF	176.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	4.816
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	4.669
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	8.092

**Call Order: 010 Proposal: T4552**

ALT	Item	Description	Unit	Quantity
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.278
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	4.797
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.925
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.154
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.239
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.237
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.222
	0713-103-102	PERMANENT TAPE, WHITE, SOLID, 8" EXIT LANE AT INTERCHANGE ON CONCRETE PAVEMENT	GM	0.222
	0713-103-133	PERMANENT TAPE, WHITE, SKIP, 12" WIDE 3'-9' DROP LANE ON CONCRETE SURFACES	GM	0.387
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.222
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.387
<b>Section 0004 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	11,005.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,095.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	330.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	97.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	19.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	1,422.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	19,647.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	32,463.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	64.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	73.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	1.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	6.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	44.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	44.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	64.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	14.000
	0715-513-145	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM WALL MOUNT, ALUMINUM, 45'	EA	10.000
	0715-515-145	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM BRIDGE MOUNT-ALUMINUM, 45'	EA	4.000
<b>Section 0005 Landscape / Peripheral</b>				
	0581- 1- 1	RELOCATE TREES AND PALMS, PALM, <14' OF CLEAR TRUNK	EA	16.000
	0581- 1- 2	RELOCATE TREES AND PALMS, PALM, >=14' OF CLEAR TRUNK	EA	71.000
	0581- 1- 5	RELOCATE TREES AND PALMS,TREES, TREES, >=5" DIAMETER AT BREAST HEIGHT	EA	1.000
	0581- 1- 7	RELOCATE TREES AND PALMS,PALMS, <14' OF CLEAR TRUNK, SABAL PALM ONLY	EA	17.000

**Call Order: 010 Proposal: T4552**

ALT	Item	Description	Unit	Quantity
	0581- 1- 8	RELOCATE TREES AND PALMS, >=14' OF CLEAR TRUNK, SABAL PALM ONLY	EA	28.000
<b>Section 0006 Intelligent Transportation System</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	7,905.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,420.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	13,215.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	35,905.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	100.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	25,200.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	1,200.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	20.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	264.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	11.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	22.000
	0633- 3- 41	FIBER OPTIC CONNECTION HARDWARE, RELOCATE SPLICE ENCLOSURE	EA	1.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	12.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	56.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	14.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	5.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	7,060.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	5,115.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	9.000
	0639- 6- 1	ELECTRICAL POWER SERVICE- TRANSFORMER FURNISH & INSTALL	EA	9.000
	0641- 2- 14	PRESTRESSED CONCRETE POLE, F&I, TYPE P-IV	EA	3.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	8.000
	0641- 3-169	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 69'	EA	6.000
	0641- 3-800	CONCRETE CCTV POLE, COMPLETE POLE REMOVAL	EA	1.000
	0646- 2-115	ALUMINUM POLE- INDEX 17900/695-001, FURNISH & INSTALL, 15'	EA	4.000
	0650- 1- 13	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 2 SECTION, 1-2 WAYS	AS	8.000
	0660- 1-112	LOOP DETECTOR INDUCTIVE, F&I, TYPE 12, 4 CH, SS, RM, TD	EA	6.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	24.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	12.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	10.000
	0660- 3- 51	VEHICLE DETECTION SYSTEM- MICROWAVE, ADJUST & MODIFY, CABINET EQUIPMENT	EA	3.000



**Call Order: 010 Proposal: T4552**

ALT	Item	Description	Unit	Quantity
	0660- 7- 11	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 1 OR 2 LANES	EA	1.000
	0670- 5-140	TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL MODEL 2070	AS	2.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	9.000
	0676- 2-400	ITS CABINET, RELOCATE	EA	1.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	6.000
	0682- 1-153	ITS CCTV CAMERA, F&I, STATIONARY, IP, HIGH DEFINITION	EA	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0684- 6- 11	WIRELESS COMMUNICATION DEVICE, FURNISH & INSTALL ETHERNET ACCESS POINT	EA	2.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	11.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	10.000
	0700- 1- 21	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013 UP TO 12 SF	AS	3.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	4.000
	0700- 6- 11	HIGHLIGHTED SIGN, F&I GROUND MOUNT- AC POWERED, UP TO 12 SF	AS	4.000
	0700- 12- 11	SIGN BEACON, F&I GROUND MOUNT- AC POWERED, ONE BEACON	AS	7.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	4.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43696215202)	LS	1.000