

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT201118	Call Order: 002	Proposal: T2788	District:02
Counties:	COLUMBIA			
Road Name:	SR 93 (I-75)			
Limits:	FROM N OF SR 47 TO S OF US 90			
Project(s):	44258115201(*)	Federal Aid No: D219167B		
Total Roadway Length:	3.645 Miles	Contract Days:	240	
Total Bridge Length:	0.039 Miles	Letting Date:	11/18/20	
Total Proposal Length:	3.684 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days (Acq. time)	

Proposal Budget Estimate: \$6,931,883.00

Please read the full advertisement

**Description:**

The improvements under this contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, highway signing, guardrail and other incidental construction on SR 93/I-75 in Columbia County from north of SR 47 to south of US 90.

**Call Order: 002 Proposal: T2788**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	282.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (44258115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44258115201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44258115201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	8,336.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	1,400.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	4,175.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	19,488.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	300.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	2,110.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	10.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,200.000
	0102-115-	TYPE III BARRICADE	ED	80.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	480.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	480.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,477.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0107- 1-	LITTER REMOVAL	AC	815.260
	0107- 2-	MOWING	AC	495.490
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44258115201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44258115201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	233.000

**Call Order: 002 Proposal: T2788**

ALT	Item	Description	Unit	Quantity
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	174.500
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44258115201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	945.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	945.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	79,791.000
	0327- 70- 15	MILLING EXIST ASPH PAVT, 2 3/4" AVG DEPTH	SY	54,171.000
	0327- 70- 20	MILLING EXIST ASPH PAVT, 3 3/4" AVG DEPTH	SY	95,350.000
	0327- 70- 33	MILLING EXIST ASPH PAVT, 7 3/4" AVG DEPTH	SY	10,141.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	6,738.800
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	25,596.100
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	6,386.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	114.300
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	1.000
	0425- 1-553	INLETS, DT BOT, TYPE E, J BOT, <10'	EA	1.000
	0425- 1-581	INLETS, DT BOT, TYPE H, <10'	EA	1.000
	0425- 1-923	INLETS, ADJACENT BARRIER, J BOTTOM, < 10'	EA	1.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	46.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	14.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	9.000
	0430-524-200	STRAIGHT CONCRETE ENDWALLS, 24", DOUBLE, 0 DEGREES, ROUND	EA	1.000
	0430-613-123	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:4 SLOPE,15"PIPE	EA	1.000
	0521- 72- 56	SHOULDER CONCRETE BARRIER, 56" PIER PROTECTION BARRIER/CRASH WALL	LF	948.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT,NON REINFORCED, 4"	SY	56.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,078.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	409.000
	0536- 5- 1	RUB RAIL FOR GUARDRAIL, SINGLE SIDED RUB RAIL	LF	303.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,613.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	4.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	2.000
	0538- 1-	GUARDRAIL RESET	LF	50.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	4.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	14.204
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	21,340.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	6.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	7.771
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	14.580
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	8.030
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44258115201)	LS	1.000

**Call Order: 002 Proposal: T2788**

ALT	Item	Description	Unit	Quantity
<b>Section 0003 Signing</b>				
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0700- 2- 17	MULTI- POST SIGN, F&I GROUND MOUNT, 201-300 SF	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	2.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	2.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44258115201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	81.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	75.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	7.285
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	14.651
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	7.286
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.328
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.355
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.046
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.078
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.152
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.078
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.152