

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT201118      Call Order: 003      Proposal: T2792      District:02

Counties: TAYLOR

Road Name: CR 361

Limits: OVER CLEARWATER CREEK BR

Project(s): 43740615201(\*)      Federal Aid No: D219148B

Total Roadway Length:	0.316 Miles	Contract Days:	365
Total Bridge Length:	0.025 Miles	Letting Date:	11/18/20
Total Proposal Length:	0.341 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60 Days (Acq. time)

Proposal Budget Estimate: \$2,953,249.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, base work, highway signing, guardrail, Bridge #380040 replacement, dredging of Clearwater Creek, roadway reconstruction, shoulder additions, and other incidental construction along CR 361 in Taylor County, 4.2 miles north of Keaton Beach.

**Call Order: 003 Proposal: T2792**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43740615201, 380040)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	321.600
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	98.400
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	90.500
	0400- 7- 1	BRIDGE DECK GROOVING	SY	605.000
	0400- 9- 1	BRIDGE DECK PLANING	SY	605.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	3.600
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	103,609.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	11,177.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	18,896.000
	0455- 35- 22	STEEL PILING, 24" DIA. PIPE	LF	1,325.000
	0455-144- 22	TEST PILES - STEEL, 24" DIA PIPE	LF	340.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	83.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	384.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	37.300
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,239.600
	0530- 74-	BEDDING STONE	TN	441.500
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	1,152.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	4.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (43740615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43740615201)	LS	1.000

**Call Order: 003 Proposal: T2792**

ALT	Item	Description	Unit	Quantity
	0102- 2-122	SPECIAL DETOUR- TEMPORARY BRIDGE, PROJECT 437406-1-52-01 (43740615201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43740615201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43740615201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	6,840.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	1,674.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	16,020.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	868.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	720.000
	0102-115-	TYPE III BARRICADE	ED	3,600.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	139.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,587.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	96.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	48.000
	0110- 1- 1	CLEARING & GRUBBING (43740615201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	2,582.000
	0120- 6-	EMBANKMENT	CY	1,710.000
	0160- 4-	TYPE B STABILIZATION	SY	4,224.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,634.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	2,356.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	2,027.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	248.700
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	433.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	77.200
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	47.000
	0430-518-100	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	744.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, NEW BRIDGE OR CONCRETE BARRIER, APPROACH TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	256.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0550- 10-110	FENCING, TYPE A, 0.0-5.0', STANDARD	LF	1,459.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	12,429.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	1,071.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.685
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.685
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43740615201)	LS	1.000
<b>Section 0003 Signing</b>				
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	2.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	4.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43740615201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.610

**Call Order: 003 Proposal: T2792**

ALT	Item	Description	Unit	Quantity
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.305
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.303
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.073
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.073