

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT201118 Call Order: 009 Proposal: T4557 District:04
 Counties: PALM BEACH
 Road Name: TRAFFIC CALMING ENHANCEMENTS
 Limits: ALONG HALL BLVD, TEMPLE BLVD AND 140TH AVE
 Project(s): 44004515201(*) Federal Aid No: D420062B
 Total Roadway Length: 2.940 Miles Contract Days: 214
 Total Bridge Length: 0.000 Miles Letting Date: 11/18/20
 Total Proposal Length: 2.940 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Calendar Days

Proposal Budget Estimate: \$617,643.00

Please read the full advertisement

Description:

The improvements under this contract consist of, but are not limited to, widening (mid-block raised islands, speed tables, raised median approach), milling and resurfacing, concrete (sidewalk, driveway, curb and gutter, patterned), pavers, asphalt (sidewalk, driveway), signing (single post, highlighted solar-powered), pavement markings (paint, thermoplastic, object markers, raised rumble strips), monitor existing structures (inspection and settlement, vibration), irrigation sleeves, and utility adjustments (manhole) along Hall Blvd., Temple Blvd. and along 140th Ave.

Call Order: 012 Proposal: T4557

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44004515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44004515201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,192.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,716.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	10,717.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	512.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,225.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	8.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44004515201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44004515201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44004515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	201.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	3.000
	0120- 1-	REGULAR EXCAVATION	CY	260.900
	0120- 6-	EMBANKMENT	CY	671.600
	0160- 4-	TYPE B STABILIZATION	SY	3,340.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,589.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	30.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT/DRIVEWAY BASE- ASPHALT MATERIAL	TN	3.800
	0327- 70- 12	MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH	SY	4,569.000

Call Order: 012 Proposal: T4557

ALT	Item	Description	Unit	Quantity
	0334- 1- 11	SUPERPAVE ASPHALTIC CONC, TRAFFIC A	TN	611.400
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	10.700
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	1.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	763.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	92.000
	0523- 1-	PATTERNED PAVEMENT, VEHICULAR AREAS	SY	19.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	30.000
	0527- 2-	DETECTABLE WARNINGS	SF	39.000
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	16.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	3,123.000
	0591- 1-200	IRRIGATION SLEEVE, 2" DIAMETER	LF	388.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.675
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	156.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	42.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.394
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44004515201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	68.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	8.000
	0700- 6- 21	HIGHLIGHTED SIGN, F&I GROUND MOUNT- SOLAR POWERED, UP TO 12 SF	AS	8.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	16.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	210.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44004515201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	460.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	248.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	42.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	375.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.830
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.249
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	2,214.000