

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT201118	Call Order: 010	Proposal: T5685	District:05
Counties:	VOLUSIA			
Road Name:	CR 4164 (OSTEEN-MAYTOWN RD)			
Limits:	FROM E OF GOBBLER'S LODGE RD TO E OF I-95			
Project(s):	44139615201(*)	Federal Aid No: D520050B		
Project(s):	44139615202	Federal Aid No: N/A		
Total Roadway Length:	11.654 Miles	Contract Days:	130	
Total Bridge Length:	0.000 Miles	Letting Date:	11/18/20	
Total Proposal Length:	11.654 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Calendar Days	
Proposal Budget Estimate:	\$1,582,330.00			

Please read the full advertisement

Description:

The improvements under this contract consist of, but not limited to, construction of paved shoulders, signing, pavement markings (paint and thermoplastic) and sod at CR-4164 (Osteen-Maytown Rd.).

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 013 Proposal: T5685

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44139615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44139615201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,200.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	34,580.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,040.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	700.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,152.000
	0104- 10- 3	SEDIMENT BARRIER	LF	22,467.000
	0110- 1- 1	CLEARING & GRUBBING (44139615201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	2,760.000
	0285-705-	OPTIONAL BASE, BASE GROUP 05	SY	15,424.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1,696.600
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	7,307.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44139615201)	LS	1.000
Section 0002 Signing				
	0546- 72- 2	GROUND-IN RUMBLE STRIPS, 8" CYLINDRICAL	GM	16.393
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	70.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	22.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	3.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	51.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	18.462
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44139615201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.753
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.843
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	10.095
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	103,525.000