

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT201118 Call Order: 012 Proposal: T6479 District:06  
 Counties: MIAMI-DADE  
 Road Name: SR 826 (NE 163RD ST) AND SR 934 (NW 81ST ST/NW 82ND ST)  
 Limits: FROM NW 2ND AVE TO NE 35TH AVE AND FROM NW 79TH ST TO NE 10TH AVE  
 Project(s): 44017715201 Federal Aid No: D619073B  
 Project(s): 44028115201(\*) Federal Aid No: D619077B  
 Total Roadway Length: 7.382 Miles Contract Days: 155  
 Total Bridge Length: 0.000 Miles Letting Date: 11/18/20  
 Total Proposal Length: 7.382 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 120 Calendar Days  
 Proposal Budget Estimate: \$676,718.00

Please read the full advertisement

Description: FLEXIBLE START

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at:  
<https://www.fdot.gov/equalopportunity/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at:  
<http://www.cmdp-bgp.com/bdi-projects.html>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: [fdot.bdi@dot.state.fl.us](mailto:fdot.bdi@dot.state.fl.us).

All Sublet work must be contracted to a small business or businesses as defined by the Department. The subcontractor must also submit a notarized Small Business Affidavit Form provided by the Department prior to the start of work.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the project's major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the Expedite application.

BDI Reference Sheet may be found at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

The improvements under this contract consist of Lighting along SR 826 (NE 163rd St.) and SR 934 (NW 81st St. / NW 82nd St.

**Call Order: 015 Proposal: T6479**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44017715201)	LS	1.000
	0101- 1-	MOBILIZATION (44028115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44017715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44028115201)	LS	1.000

**Call Order: 015 Proposal: T6479**

ALT	Item	Description	Unit	Quantity
	0102- 60-	WORK ZONE SIGN	ED	4,030.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,115.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,630.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	155.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	366.000
	0110- 1- 1	CLEARING & GRUBBING (44017715201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44028115201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.030
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	296.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	208.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	68.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	41.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44017715201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44028115201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
<b>Section 0003 Lighting</b>				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	5,018.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	67.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	5,589.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	14,075.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	8,475.000
	0715- 4- 12	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT	EA	10.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	3.000
	0715- 4- 15	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT	EA	5.000
	0715- 4- 22	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 35' MOUNTING HEIGHT	EA	1.000
	0715- 4- 24	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 45' MOUNTING HEIGHT	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	64.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	51.000
	0715-511-135	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 35'	EA	4.000
<b>Section 0004 Signalization</b>				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000