

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT201118 Call Order: 013 Proposal: T6497 District:06
 Counties: MIAMI-DADE
 Road Name: SR 934 (NW 79 ST), SR 25 AND SR 934 (E 25TH ST)
 Limits: FROM PALM AVE TO NE 5TH AVE, FROM W 18TH AVE TO NE 2ND AVE AND AT NW 22ND AVE
 Project(s): 44017725201 Federal Aid No: D619082B
 Project(s): 44516715201 Federal Aid No: D619078B
 Project(s): 44516815201(*) Federal Aid No: D619079B
 Total Roadway Length: 15.564 Miles Contract Days: 150
 Total Bridge Length: 0.000 Miles Letting Date: 11/18/20
 Total Proposal Length: 15.564 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 120 Calendar Days
 Proposal Budget Estimate: \$625,039.00

Please read the full advertisement

Description: FLEXIBLE START

The improvements under this contract consist of Lighting improvements along SR (NW 79 St.), SR 25 and SR 934 (E 25th St.).

Call Order: 016 Proposal: T6497

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44017725201)	LS	1.000
	0101- 1-	MOBILIZATION (44516715201)	LS	1.000
	0101- 1-	MOBILIZATION (44516815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44017725201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44516715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44516815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	4,310.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,415.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,005.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	175.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	400.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44516715201)	LS	1.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44516815201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44516715201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44516815201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.150
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	292.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	245.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	46.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44017725201)	LS	1.000

Call Order: 016 Proposal: T6497

ALT	Item	Description	Unit	Quantity
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44516715201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44516815201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,979.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	51.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	11,457.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	2,331.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	3.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	3.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	143.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	22.000
	0715- 11-216	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, PENDANT/TEARDROP	EA	13.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	20.000
	0715-511-140	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 40'	EA	2.000
	0715-516-125	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, POLE TOP MOUNT- ALUMINUM, 25'	EA	1.000
Section 0003 Signalization				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000