

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT201118 Call Order: 016 Proposal: T7466 District:07
 Counties: HILLSBOROUGH
 Road Name: SR 573 (S DALE MABRY HWY)
 Limits: FROM N OF PINWOOD ST TO S OF GANDY BLVD
 Project(s): 43764615201(*) Federal Aid No: D720033B
 Total Roadway Length: 1.375 Miles Contract Days: 120
 Total Bridge Length: 0.000 Miles Letting Date: 11/18/20
 Total Proposal Length: 1.375 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Calendar Days
 Proposal Budget Estimate: \$2,600,000.00

Please read the full advertisement

Description:

The improvements under this contract consist of design of median modifications and turn lanes on SR 573 (S. Dale Mabry Hwy.).

Call Order: 018 Proposal: T7466

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43764615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43764615201)	LS	1.000
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (43764615201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	24.000
	0102- 60-	WORK ZONE SIGN	ED	14,880.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	12,720.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	6,970.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	240.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	524.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	254.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	480.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	480.000
	0102-115-	TYPE III BARRICADE	ED	2,400.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	120.000
	0104- 10- 3	SEDIMENT BARRIER	LF	86.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	42.000
	0107- 1-	LITTER REMOVAL	AC	34.000
	0107- 2-	MOWING	AC	18.290
	0110- 1- 1	CLEARING & GRUBBING (43764615201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,006.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,006.500
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43764615201)	LS	1.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	15,535.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	2,941.000

Call Order: 018 Proposal: T7466

ALT	Item	Description	Unit	Quantity
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	2,531.700
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,142.100
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	3,599.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	63.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	265.000
	0520- 5- 12	TRAFFIC SEPARATOR CONCRETE-TYPE I, 6' WIDE	LF	2,500.000
	0520- 5- 16	TRAFFIC SEPARATOR CONCRETE- TYPE I, 8.5' WIDE	LF	3,056.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	417.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	75.000
	0527- 2-	DETECTABLE WARNINGS	SF	89.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,757.000
	0591- 1-200	IRRIGATION SLEEVE, 2" DIAMETER	LF	241.000
	0591- 1-600	IRRIGATION SLEEVE, 6" DIAMETER	LF	241.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	9.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	85.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	3.000
	0695- 3- 11	TRAFFIC MONITORING SITE SPEED/CLASSIFICATION UNIT, FURNISH & INSTALL, VOLUME SPEED AND CLASSIFICATION	AS	3.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	3.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.334
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.579
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	289.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,908.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	600.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.421
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	62.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.597
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.153
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43764615201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	62.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISIBILITY MEDIAN	EA	39.000
	0706- 1- 1	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS	EA	484.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	176.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	452.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43764615201)	LS	1.000

Call Order: 018 Proposal: T7466

ALT	Item	Description	Unit	Quantity
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	1.474
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	447.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,898.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	749.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.360
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	61.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.141
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.333
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.005
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.523
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	9.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0654- 2- 21	RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR POWERED, COMPLETE SIGN ASSEMBLY- SINGLE DIRECTION	AS	6.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	3.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	2.000