



**Call Order: 019 Proposal: T3772**

ALT	Item	Description	Unit	Quantity
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	3,909.800
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,533.000
	0327- 70- 12	MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH	SY	46,136.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	7,229.000
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-9.5, PG 76-22	TN	3,668.900
	0400- 1- 11	CONCRETE CLASS I, RETAINING WALLS	CY	342.900
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	15,480.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	1.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	23.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	2.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	71.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	0.100
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	126.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	3,431.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,141.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	2,322.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	1,108.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	6.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	812.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	978.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	172.000
	0527- 2-	DETECTABLE WARNINGS	SF	348.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	1,776.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	6.662
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	13,034.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,760.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	5.250
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	64.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	6.166
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	62.000
	0914-550- 16	FENCING- PEDESTRIAN BARRIER, P1 STEEL LOOP, PROJECT 443769 -1-52-01	LF	2,078.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44376915201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44376915202)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	31.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	7.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	10.000

**Call Order: 019 Proposal: T3772**

ALT	Item	Description	Unit	Quantity
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	34.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44376915201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	6,517.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	880.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	32.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	31.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	3,578.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.331
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.625
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.083
<b>Section 0003 Signalization</b>				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,247.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	14.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	81.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	11.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	751.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	11.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	30.000
	0649- 21- 1	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 30'	EA	4.000
	0649- 21- 2	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 30'-30'	EA	7.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	2.000
	0649- 21- 5	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 40'-40'	EA	1.000
	0649- 21- 7	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 50'-30'	EA	1.000
	0649- 21- 8	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 50'-40'	EA	3.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	28.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	4.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	16.000
	0654- 1- 10	IN ROADWAY LIGHT ASSEMBLY, FURNISH & INSTALL- AC POWERED, COMPLETE CROSSING	AS	7.000
	0654- 2- 11	RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- AC POWERED, COMPLETE SIGN ASSEMBLY- SINGLE DIRECTION	AS	14.000
	0654- 2- 15	RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- AC POWER, MAST ARM MOUNT RRFB SIGN ASSEMBLY	AS	14.000

**Call Order: 019 Proposal: T3772**

ALT	Item	Description	Unit	Quantity
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	7.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	7.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	32.000
	0670- 5-112	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 2 PREEMPTION	AS	7.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	3.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	7.000
	0684- 6- 12	WIRELESS COMMUNICATION DEVICE, FURNISH & INSTALL ETHERNET SUBSCRIBER UNIT	EA	7.000
	0685- 1- 14	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION WITH CABINET	EA	7.000
<b>Section 0004 Landscape / Peripheral</b>				
	0101- 1-	MOBILIZATION (44376915203)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44376915203)	LS	1.000
	0580- 1- 1	LANDSCAPE COMPLETE- SMALL PLANTS (44376915203)	LS	1.000
	0590- 70-	IRRIGATION SYSTEM (44376915203)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44376915203)	LS	1.000
<b>Section 0005 Utilities</b>				
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	19.000
	0425- 6-	VALVE BOXES, ADJUST	EA	18.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44376915204)	LS	1.000