

Call Order: 003 Proposal: T7438

ALT	Item	Description	Unit	Quantity
	0104- 7-	SEDIMENT BASIN / CONTAINMENT SYSTEM	EA	4.000
	0104- 9-	SEDIMENT BASIN / CONTAINMENT SYSTEM- CLEANOUT	EA	4.000
	0104- 10- 3	SEDIMENT BARRIER	LF	23,059.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	2,174.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	3.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000
	0104- 19-	CHEMICAL TREATMENT- POWDERED, FOR EROSION CONTROL	SY	2,065.000
	0107- 1-	LITTER REMOVAL	AC	1,542.450
	0107- 2-	MOWING	AC	1,466.260
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (25632425201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (25632425201)	LS	1.000
	0108- 3-	MONITOR EXISTING STRUCTURES- GROUNDWATER MONITORING (25632425201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (25632425201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	17,733.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	40.000
	0120- 1-	REGULAR EXCAVATION	CY	220,779.000
	0120- 4-	SUBSOIL EXCAVATION	CY	81.000
	0120- 6-	EMBANKMENT	CY	134,637.000
	0120- 74-	SURCHARGE EMBANKMENT	CY	665.000
	0141- 70-	SETTLEMENT PLATE ASSEMBLY	AS	3.000
	0160- 4-	TYPE B STABILIZATION	SY	135,129.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	28,804.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	1,543.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	68,326.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT/DRIVEWAY BASE- ASPHALT MATERIAL	TN	1,693.200
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	1,076.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	22,942.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	6,654.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	23,615.200
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	4,306.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	63.800
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	3.000
	0425- 1-531	INLETS, DITCH BOTTOM, TYPE C MODIFIED- BACK OF SIDEWALK, <10'	EA	5.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	63.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	14.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	14.000
	0425- 1-581	INLETS, DT BOT, TYPE H, <10'	EA	2.000
	0425- 1-582	INLETS, DT BOT, TYPE H, >10'	EA	1.000
	0425- 1-589	INLETS, DT BOT, TYPE H, MODIFY	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	11.000
	0425- 1-703	INLETS, GUTTER, TYPE S, J BOTTOM <10'	EA	4.000

Call Order: 003 Proposal: T7438

ALT	Item	Description	Unit	Quantity
	0425- 2- 41	MANHOLES, P-7, <10'	EA	4.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	8.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	1.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	4.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	1.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	5.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	71.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	242.000
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	141.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	4,109.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	7,773.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	3,590.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	1,911.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	456.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	352.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	170.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	56.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	3,536.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	2,936.000
	0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/C	LF	774.000
	0430-175-236	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 36"S/C	LF	220.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-524-402	STRAIGHT CONCRETE ENDWALLS, 24", QUAD, 0 DEGREES, ELLIPTICAL	EA	2.000
	0430-530-302	STRAIGHT CONCRETE ENDWALLS, 30", TRIPLE, 0 DEGREES, ELLIPTICAL	EA	2.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	11.400
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	2.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	1.000
	0430-982-140	MITERED END SECTION, OPTIONAL ROUND, 42" CD	EA	1.000
	0430-982-143	MITERED END SECTION, OPTIONAL ROUND, 60" CD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	4.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	3.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	9.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	7.000
	0430-984-633	MITERED END SECT, OPTIONAL /ELLIP/ARCH, 30" SD	EA	1.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	90.000
	0515- 2-211	PEDESTRIAN / BICYCLE RAILING, STEEL, 42" TYPE 1	LF	15.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	5,631.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	717.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	227.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	3,105.000

Call Order: 003 Proposal: T7438

ALT	Item	Description	Unit	Quantity
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	196.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	2,035.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	249.000
	0524- 3-	CONC CORE DITCH BLOCKS	CY	1.800
	0527- 2-	DETECTABLE WARNINGS	SF	439.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	129.900
	0530- 74-	BEDDING STONE	TN	95.700
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,869.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	1,536.000
	0536- 73-	GUARDRAIL REMOVAL	LF	726.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	3.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	1,827.000
	0550- 10-228	FENCING, TYPE B, 5.1-6.0, RESET EXISTING	LF	20.000
	0550- 60-214	FENCE GATE, TYPE B, SINGLE, 18.1-20.0' OPENING	EA	1.000
	0550- 60-222	FENCE GATE, TYPE B, DOUBLE, 6.1-12.0' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	206,457.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	23,138.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	46.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	100.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	16.041
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	96.016
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	287.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	645.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.650
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	44.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	13.812
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.078
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,441.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.100
	0999- 16-	PARTNERING, DO NOT BID	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	12.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (25632425201)	LS	1.000

Call Order: 003 Proposal: T7438

ALT	Item	Description	Unit	Quantity
	Section 0002 Signing			
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	3.969
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	37.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	16.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	16.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	31.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	9.000
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	3.452
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	6.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	8.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISIBILITY MEDIAN	EA	5.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	40.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	756.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (25632425201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	723.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,234.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	382.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.773
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	86.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,322.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.223
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	653.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	6.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	6.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	6.775
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.739
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	4.664
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	1.317
	0711- 15-202	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES YELLOW, SOLID, 8"	GM	0.234
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	936.000

Call Order: 003 Proposal: T7438

ALT	Item	Description	Unit	Quantity
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	5.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	143.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	1.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	1.000
	0650- 1- 70	VEHICULAR TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	4.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
Section 0004 Utilities				
	0400- 2- 12	CONCRETE, CLASS II, TRENCH SLAB	CY	31.700
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (25632425601)	LS	1.000
	1050- 14-004	UTILITY PIPE, RELOCATE, 8-19.9"	LF	360.000
	1050- 15-001	UTILITY PIPE, ADJUST/MODIFY, 0 - 1.9"	LF	95.000
	1050- 15-002	UTILITY PIPE, ADJUST/MODIFY, 2 - 4.9"	LF	50.000
	1050- 15-004	UTILITY PIPE, ADJUST/MODIFY, 8 - 19.9"	LF	240.000
	1050- 16-003	UTILITY PIPE,REMOVE & DISPOSE, 5-7.9"	LF	4,036.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	3,316.000
	1050- 16-005	UTILITY PIPE,REMOVE & DISPOSE, 20-49.9"	LF	52.000
	1050- 18-002	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 2- 4.9"	LF	507.000
	1050- 18-003	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 5- 7.9"	LF	460.000
	1050- 31-206	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	530.000
	1050- 31-208	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 8"	LF	420.000
	1050- 31-212	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 12"	LF	400.000
	1050- 31-216	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 16"	LF	1,710.000
	1050- 42-208	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 8"	LF	320.000
	1050- 42-212	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 12"	LF	180.000
	1050- 61-116	UTILITY PIPE- STEEL, FURNISH & INSTALL, CASING, 16"	LF	64.000
	1055- 11-414	UTILITY FITTINGS, F&I, DI/CI, ELBOW, 8 - 19.9"	EA	43.000
	1055- 11-444	UTILITY FITTINGS, F&I, DI/CI, UNION, 8 - 19.9"	EA	20.000
	1055- 11-454	UTILITY FITTINGS, F&I, DI/CI, CAP/PLUG, 8 - 19.9"	EA	3.000
	1060- 16-	UTILITY STRUCTURE, BELOW GROUND, REMOVE&DISPOSE CONTRACTOR TAKES OWNERSHIP	EA	1.000
	1060- 21- 10	UTILITY STRUCTURE- ABOVE GROUND, 0-1 CY PAD, WITHOUT COVER	EA	3.000
	1060- 25-	UTILITY STRUCTURE, ABOVE GROUND, ADJUST & MODIFY	EA	7.000
	1080- 21-500	UTILITY FIXTURE, VALVE/METER BOX, ADJUST	EA	29.000

Call Order: 003 Proposal: T7438

ALT	Item	Description	Unit	Quantity
	1080- 23-112	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 12"	EA	3.000
	1080- 24-102	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 2"	EA	1.000
	1080- 24-106	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"	EA	1.000
	1080- 24-108	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 8"	EA	2.000
	1080- 24-112	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 12"	EA	2.000
	1080- 24-116	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 16"	EA	3.000
	1080- 26-102	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 2"	EA	4.000
	1080- 27-112	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 12	EA	1.000
	1080- 27-116	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 16	EA	1.000
	1080- 29-106	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 6"	EA	40.000
	1080- 29-108	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 8"	EA	43.000
	1080- 29-112	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 12"	EA	33.000
	1080- 29-116	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 16"	EA	142.000
	1644-700-	FIRE HYDRANT, ADJUST & MODIFY	EA	2.000
	1644-800-	FIRE HYDRANT, RELOCATE	EA	1.000