

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: CT200930 Call Order: 011 Proposal: T7463 District:07  
 Counties: PINELLAS  
 Road Name: SR 595 (ALT US 19/SEMINOLE BLVD)  
 Limits: FROM N OF 101ST AVE N TO SR 686 (EAST BAY DR)  
 Project(s): 43762415201(\*) Federal Aid No: D720015B  
 Project(s): 43762415202 Federal Aid No: D720015B  
 Total Roadway Length: 3.587 Miles Contract Days: 200  
 Total Bridge Length: 0.000 Miles Letting Date: 09/30/20  
 Total Proposal Length: 3.587 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 120 Calendar Days  
 Proposal Budget Estimate: \$5,563,681.00

Please read the full advertisement

Description: Flexible Start

The improvements under this contract consist of milling and resurfacing, widening, base work, drainage improvements, curb and gutters, sidewalks, signing and pavement markings, portable traffic monitoring site(s), and signalization on SR 595 (Alternate US 19 /Seminole Blvd.).

**Call Order: 011 Proposal: T7463**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43762415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43762415201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	13.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	624.000
	0102- 60-	WORK ZONE SIGN	ED	30,199.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	685.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	147,898.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	48,515.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	400.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	1,938.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	414.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,600.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,600.000
	0102-115-	TYPE III BARRICADE	ED	19,110.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,657.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	4.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	142.000
	0107- 1-	LITTER REMOVAL	AC	62.370
	0107- 2-	MOWING	AC	9.780
	0110- 1- 1	CLEARING & GRUBBING (43762415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43762415202)	LS	1.000

**Call Order: 011 Proposal: T7463**

ALT	Item	Description	Unit	Quantity
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	4,432.000
	0120- 1-	REGULAR EXCAVATION	CY	415.100
	0120- 6-	EMBANKMENT	CY	254.800
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	10,026.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	170,145.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,768.900
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	14,479.500
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	1.000
	0425- 1-321	INLETS, CURB, TYPE P-2, <10'	EA	1.000
	0425- 1-325	INLETS, CURB, TYPE P-2, PARTIAL	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	2.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	1.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	3.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0425- 2- 73	MANHOLES, J-7, PARTIAL	EA	1.000
	0425- 2- 93	MANHOLES, J-8, PARTIAL	EA	2.000
	0425- 4-	INLETS, ADJUST	EA	1.000
	0430-175-112	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 12"S/CD	LF	4.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	105.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	176.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	30.000
	0432- 3- 2	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 18"	EA	7.000
	0432- 3- 4	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 24"	EA	2.000
	0440- 73- 2	UNDERDRAIN OUTLET PIPE, 6"	LF	14.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	20.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	165.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	4,008.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	83.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	187.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	1,435.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,024.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	889.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,154.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	660.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	55.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	385.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	10.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	25.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	25.000
	0695- 7-162	TRAFFIC MONITORING SITE CABINET, F&I, TYPE 3, 2 PANE BACK, PEDESTAL MOUNT	EA	4.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	13.271

**Call Order: 011 Proposal: T7463**

ALT	Item	Description	Unit	Quantity
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.291
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	44.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	33.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	759.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	4.103
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.402
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	117.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	15.266
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	25.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.870
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43762415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43762415202)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	67.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	15.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	15.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	32.000
	0700- 1- 74	SINGLE POST SIGN, F&I CUSTOM, 31+ SF	AS	1.000
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	8.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISIBILITY MEDIAN	EA	62.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	48.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	1,175.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43762415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	7,586.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	153.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,722.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.111
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	141.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	139.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.036
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	4,714.000

**Call Order: 011 Proposal: T7463**

ALT	Item	Description	Unit	Quantity
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	6.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	9.253
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.493
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	11.814
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.852
<b>Section 0003 Signalization</b>				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,927.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	4.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	42.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	23.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	10.000
	0649- 21- 16	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 70'-30'	EA	1.000
	0649- 21- 26	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 78'-70'	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	12.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	20.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	3.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	4.000
	0660- 1-103	LOOP DETECTOR INDUCTIVE, F&I, TYPE 3	EA	33.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	89.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	25.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	4.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	6.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	6.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	16.000
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	6.000